

13-31-16W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BARBARA OIL CO.
Farm-Robbins-Gallup "D" No. 1

SEC. 13 T. 31 R. 16W
C NW

Total Depth. 4830'
Comm. 9-17-60 Comp. 10-7-60
Shot or Treated.
Contractor. Pickrell Drilg. Co.
issued. 12-24-60

County Comanche



Elevation. 1969' RB

CASING:

13 3/8" 319' cem w/300 sx.
7" 4829' cem w/200 sx.

Production. 17,500,000 CFG

Meas. from top of RB.

Figures Indicate Bottom of Formations.

top soil, rock	35
sand	50
red shale, shells	325
red bed, shale	885
Anhydrite	915
shale	1030
salt, shale, shells	1065
shale, shells	1900
lime, shale	2040
lime	2685
lime, shale	3025
shale, lime	3180
lime, shale	3480
shale, lime	3565
lime, shale	3875
lime	3980
lime, shale sand	4035
sand, shale, lime	4110
lime	4138
lime, shale	4225
lime	4271
lime, shale	4310
lime	4390
shale, lime	4430
lime	4695
lime, shale	4728
Mississippi	4830
Total Depth	

TOPS: SCOUT

Heebner	3992
Toronto	4005
Douglas	4029
Lansing	4182
Base Kansas City	4592
Marmaton	4638
Mississippi	4727