

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas



23-31-16W

Company. BARBARA OIL COMPANY
Farm. Robbins Unit No. 1

SEC. 23 T. 31 R. 16W
CSE SE

Total Depth. 4958
Comm. 4-21-53 Comp. 5-21-53
Shot or Treated.
Contractor. R. C. Patton Co.
Issued. 7-11-53

County Comanche
KANSAS



CASING:
10 3/4" 291' cem. w/250 sx
7" 4935' cem. w/250 sx

Elevation. 2035

Production. 9,682,000 Gas

Figure 1. Log of Formations.

clay surface	25
sand gry	45
shale hrd gry	63
sandy shale gry	140
red bed	270
lime	294
red bed	950
shale & shells	1450
salt & shale	1550
shale, shells	2200
shale & lime	2315
lime, shale & shells	2365
anhydrite & shale	2400
lime	2425
lime & shale	3090
shale & shells	3160
lime & shale	3422
lime	3452
lime & shale	3495
lime	3902
lime & shale	3930
shale	3950
lime & shale	4240
lime	4245
sand	4265
lime sandy	4289
lime	4315
sand	4324
lime	4730
lime & shale	4848
sand, shale	4865
shale, sand, lime	4914
lime & shale	4920
shale	4935
cherty lime	4958
Total Depth	

Scout Tops:
Douglas
Lansing
Miss. Lime
Base Miss. Lime

4315
4326
4935
4950

