


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - J. M. Huber Corporation
Farm - Ferrin No. 1

SEC. 10 T. 31S R. 17W
C NW NE

Total Depth. 5595½ N. S.
Comm. 6-25-47 Comp. 7-30-47
Shot or Treated.
Contractor. J.M. HUBER CORPORATION
Issued. 9-13-47

County. Comanche
KANSAS



CASING:
10" @ 880'

Elevation. 2077 ft act

Production. Dry and abandoned

Figures Indicate Bottom of Formations.

Shale and sand	70	Lime Broken	5295
Sand, gyp, shells	400	Lime	5298
Red bed and shells	680	Lime cherty	5347
Red bed and gyp shells	880	Lime and chert	5370
Red bed - shells	980	Lime and shale	5399
Red bed shale and shells	1165	Lime	5434
Salt shale and shells	1300	Lime chert	5467
Shale and shells	1600	Sandy dolo - sand and shale	5505
Shale and shells and salt beds	1865	Sand and shale	5512
Lime and shale	2050	Sandy shale - shells	5555
Shale and lime streaks	2220	Shale and sand	5563
Lime and shale streaks	2385	Sand and lime	5566
Lime and shale	2445	Arbuckle lime	5588
Lime and shale streaks	2490	Lime (Hard)	5595½
Shale and shells	2515	TOTAL DEPTH	5595½ N.S.
Lime and shale	2630		
Lime - shale streaks	2705	TOPS:	
Shale and lime streaks	2740	Blaine	300
Shale	2805	Anyhdrite	970
Lime, shale streaks	2865	Limestone Section	4058
Shale and lime	2915	Lansing	4301
Lime and shale	2990	Mississippi Lime	4986 Corr
Lime, shale streaks	3150		
Lime and shale	3460	HDST	5017-60, open 1 hr. rec. 350'
Lime-shale streaks	3520		mud, 2150' salt water. sli.
Lime and shale	3650		gas cut, 880.
Lime	3710	HDST	5086-99 open 1 hr. rec. 90'
Lime and shale	3755		mud, N.S.
Broken lime	3825	Top Viola	5267
Lime soft	3866	HDST	5272-80 open 1 hr. rec. 25'
Lime	3895		mud, no show.
Lime broken	3960	Top Simpson	5462
Lime	4040	HDST	5490-5512, open 25 min. rods
Shale and lime	4095		12' mud, N.S.
Lime w/ shale streaks	4145	Arbuckle	5566' D&A.
Lime and shale	4185		
Lime and shale streaks	4240		
Lime and shale	4435		
Lime and shale streaks	4480		
Lime and shale	4520		
Lime	4530		
Lime and shale	4750		
Lime shale streaks	4785		
Lime and shale	4955		
Shale and shells	4980		
Lime	4990		
Mississippi Chat lime	5010		
Cherty lime and chat w/ shale streaks	5055		
Cherty lime	5060		
Chat lime and shale	5099		
Chat lime	5116		
Chat shale	5145		
Lime and chert	5179		
Lime and chat	5204		
Chert-chat	5226		
Lime and chert	5260		
Lime	5280		