

East Murdock
Wichita, Kansas

508 East Murdock
Wichita, Kansas

30-31S-17W

JUN 28 1969

JUN 2 1969

DRILLER'S LOG

WELL NAME: Baker "B" No. 1; COMPANY OPERATING: Anadarko Production Company
ADDRESS of COMPANY: Box 351 Liberal, Kansas 67901

WELL LOCATION: C 1/4 SW 1/4 NE 1/4,

3300 ft. North of South line,

3148 ft. East of West line: Sec. 30, Twp. 31S, Rge. 17W, Comanche County, Kansas

DRILLING STARTED 4-14, 19 69; DRILLING COMPLETED 4-30, 19 69

WELL COMPLETED 5-9, 19 69; WELL CONNECTED _____, 19 _____

ELEVATION: 2083 ft. Ground Level; CHARACTER OF WELL (Oil, Gas, or Dry Hole) Dry Hole

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION

Name	From	To	No. of Shots	Gallons Used	Kind Used
Mississippian	5050'	5058'	16	1000	15% N.E.

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8 5/8"	1030'	600	None
4 1/2"	5239'	160	None

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Clay & Sand	0'	125'			
Redbed	125'	1022'			
Anhydrite	1022'	1031'			
Shale & Redbed	1031'	1295'			
Shale & Shells	1295'	2055'			
Shale w/Lime streaks	2055'	2274'			
Lime & Shale	2274'	4650'			
Lime	4650'	5240'			
Total Depth	5240'				

RESULTS of INITIAL PRODUCTION TEST: _____