

PT

KANSAS *away*

WELL COMPLETION REPORT AND DRILLER'S LOG

WICHITA BRANCH

S. 30 T. 31 R. 17 ^{8K} _W

Loc. C N/2 NW NE

County Comanche

API No. 15 — 033 — 20,378
County Number

Operator

Anadarko Production Company

Address

P. O. Box 351, Liberal, Kansas 67901

Well No.

#1

Lease Name

KENNEDY "C"

Footage Location

330 feet from (N) (X) line 1980 feet from (E) (X) line

Principal Contractor

Gabbert-Jones, Inc.

Geologist

Bob Posey

Spud Date

10/5/80

Date Completed

1/4/81

Total Depth

5150'

P.B.T.D.

5000'


Directional Deviation

not applicable

Oil and/or Gas Purchaser

Dry Hole

640 Acres
N



Locate well correctly

Elev.: Gr. 2078'

DF 2084' KB 2085'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	24#	420'	Common	300	3% Cacl
Production	7-7/8"	4-1/2"	10.5#	5144'	Litewate Pozmix	25 130	SS

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	.46 Jet	5036-44'
			2	.46 Jet	4902-05'

TUBING RECORD

Size	Setting depth	Packer set at
2-3/8"	4990'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Squeexed w/100 sxs cmt	5036-5044'
A/500 gal 15% MCA	4902-4905'

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
DRY HOLE	-0-				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	-0- bbls.	-0- MCF	21 bbls.	-0- CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
-0-			4902-4905'		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Anadarko Production Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. #1	Lease Name KENNEDY "C"	Dry Hole
S <u>30</u> T <u>31</u> R <u>17</u> ^E / _W		


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand	0'	160'		
Redbed	160'	428'		
Redbed-Shale	428'	1180'		
Shale	1180'	2255'		
Shale-Lime	2255'	2590'		
Lime-Shale	2590'	3825'		
Lime	3825'	5150'		
Total Depth		5150'		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	
	Signature
	Paul Campbell, Division Production Manager
	Title
	May 20, 1981
	Date