

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

503 East Murdock,

Wichita, Kansas


Company- UNITED PRODUCING CO., INC.
Farm- McCleary No. 1

McCrary

SEC.

35-31 R. 18W
C NW SETotal Depth. 6051
Comm. 5-18-53 Comp. 6-20-53
Shot or Treated.
Contractor.
Issued. 1-23-54

County

Commanche
KANSAS

CASING:

20" 230' com. w/700 sx
13 3/8" 517' com. w/600 sx
8 5/8" 2506' com. w/400 sx
5 1/2" 5242' com. w/250 sx

Elevation. 2125'

Production. Dry

Figures Indicate Bottom of Formations

sand & surface clay	85	limo & shale	6051
sand, clay & shells	150	Total Depth	
sand & shale	161		
sand	260	TOPS:	
sand & shale	290	SCOUT	SCH.
sand, gravel & red bed	330	Kansas City	4776
		Marmaton	4868
		Mississippi Lim	5115
sand & red bed	517	Viola	5532
red bed & shells	611	Viola Dolomite	5620
red bed, shale & shells	761	Simpson	5817
		1st Simpson Sand	5870
red bed, shale, shells,		Arbuckle	5982
& anhydrite	954		
shale & anhydrite	1003		
anhydrite	1132		
shale & anhydrite	1428		
red bed & anhydrite	1650		
shale, anhydrite, limo			
& salt	1700		
shale, anhydrite,			
shells & salt	1770		
shale, anhydrite &			
salt	1985		
shale, anhydrite	2305		
anhydrite, shale &			
salt	2337		
anhydrite, shale & limo			
	2398		
shale & limo	2510		
limo	2570		
limo & sand	2700		
sandy limo & shale	2735		
sandy shale & limo	2953		
limo & shale	4358		
limo	4533		
limo, cherty	4547		
limo & shale	4624		
limo & shale, cherty	4660		
limo, cherty	4678		
limo	4973		
limo, cherty	4975		
limo	4977		
limo cherty	5037		
limo	5248		
limo, cherty & shale	5294		
limo	5380		
limo, cherty & shale	5423		
limo & chert	5515		
limo, cherty	5536		
limo	5609		
limo & chert	5710		
limo	5791		
limo & chert	5806		
limo & shale	5847		
limo, cherty	5864		
limo	5866		
limo & sand	5897		
limo & shale	5970		
shale, sand & limo	6002		