

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

17-31-18W


15-033-00025

Company- E. K. CAREY DRILLING CO.
Farm- Swarner No. 1

SEC. 17 T. 31 R. 18W
NW NW NW

Total Depth. 5250'
Comm. 3-3-58 Comp. 3-19-58
Shot or Treated.
Contractor. Capitt Drlg., Inc.
Issued. 4-26-58

County Comanche
KANSAS



CASING:
8 5/8" 489' cem w/325 sx.

Elevation. 2215' RB

Production. Dry

Figures indicate Bottom of Formations.

clay & sand	190
shale & lime	489
red bed	885
red bed & shells	1375
shale & lime	2119
lime & shale	2720
lime	2795
lime & shale	3075
shale & lime	3175
shale, lime, chalk strks	3310
shale & lime	3384
shale & shells	3530
shale	3743
shale & lime	3864
lime	3954
lime & shale	4055
shale & lime	4417
shale	4453
lime & shale	4555
lime	5050
chert	5078
lime	5250 RTD
Total Depth	

TOPS:

Heebner	4274
Douglas	4381
Missouri	4452
Lansing-Kansas City	4468
Marmaton	4894
Mississippi	5143

#2 5101-31, open 30 min. weak blow for 15 min.,
died. Recovered 20' mud. IFP 35#, FFP 50#,
BHP 62#/30.

#3 5144-80, open 1 hr., strong blow throughout,
Recovered 10' mud. IFP 40#, FFP 40#, BHP 310#/30.

DRILL STEM TESTS:

#1 5077-5111, open 1 hr., 10 min., strong
initial blow. Tool appeared to be plugging
flushed tool e times, blow dead when tool
shut in. Recovered 380' mud. IBHP 375#/30,
IFP 45#, FFP 130#, BHP 780#/30.