


KANSAS CORPORATION COMMISSION

WELL RECORD

3-31-18W

(Mail to Kansas Geological Survey, 4150 Monroe Street, Wichita, Kansas 67209)



API#15-033-20,116

Lease Name: Griffith "B" Well No. 2 *h*
 Well Located: 560'FWL & 1980'FSL *Comanche Co.*
 SEC 3 TWP 31S RGE 18W
 Operator: Anadarko Production Company
 Address: Box 351 Liberal, Kansas 67901
 Elevation: Ground 2094.0 D.F. K.B.
 Type Well: (Oil, gas, dry hole) OIL

Drilling Commenced: 2/9 19 72 Drilling Completed: 2/23 19 72
 Well Completed: 3/2 19 72 Total Depth 5110
 Initial Production: 76.5 BF in 6 hours 20% Water.

Casing Record

Size: 8 5/8 Set at 455' Size: 2 3/8 Set at 5012
 Size: 4 1/2 Set at 5109' Size: Set at

Liner Record

Size: Set from To

Cementing

Casing Size	Sacks	Type Cement and Additives
8 5/8	400	Common 2% CaCl
4 1/2	140	Salt Sat. Pozmix + .5% CFR - 2
2 3/8	SN @ 4997'	

Perforations

Formation	Perforated Interval and Number Shots
Mississippi	4994 - 5001 W/2 SPF

Electric Log Run (Show type log and depths covered)

Schlumberger - Dual Induction - Laterlog (452 - 5101')
 Borehole Compensated Sonic Log - Gamma Ray (2350 - 5106')

3-31-18

62155

DST #2 4993 - 5033' (Mississippi)
15 minute PF W/SB, incr. to GB. TO 35 minute W/GB
thruout. Recovered 105' O&GCDM + 30' OW&GCDM.
ISIP 1464# (40), PFP's 44-88#, FP 88-133#, FSIP 1367#
(40).

62155

RTD

Swabbed 76.5 BF in 6 hours 20% Water.

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION