

5-31-18W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- SOCONY MOBIL OIL CO.  
Farm- Mabel Robinson "A" No. 1

SEC. 5 T. 31 R. 18  
C W/2 NE NW

Total Depth. 5140'  
Comm. 4-28-58 Comp. 6-19-58  
Shot or Treated.  
Contractor. Capitt Drlg.  
Issued. 4-1-61

County Comanche  
KANSAS



Elevation. 2149' GL

Production. 98 BO, 15% Wtr.  
& 267 MCF

Figures Indicate Bottom of Formations.

shale & sand	160
redbed & shells	910
shale & shells	1190
shale & lime	1655
shale & shells	1945
shale, shells & lime	2180
lime & shale	2585
lime	2672
lime & shale	2749
lime	2935
lime & shale	3145
lime	3167
sandy lime & shale	3210
shale & lime	3542
lime & shale	3860
lime	3897
lime & shale	3918
lime	4050
shale & lime	4130
lime & shale	4430
lime	4824
lime & shale	4885
lime	5140
Total Depth	

TOPS:  
Lansing-Kansas City 4405  
Marmaton 4846  
Mississippi (Warsaw) 5038

Acidized perf. 5071-82' w/250 gals.  
MCA, Max. press. 1350#, min. press.  
675#, Rate 1/2 BPM, used 117 BLO, 5 min  
SI 400#.

Acidized perf. 5071-82' w/1000 gal. 15%  
reg. acid, hole filled w/107 BLO, Max.  
press. 1000#, Min. & final press. 600#,  
rate 2 1/2 BPM.

Acidized perf. 5048-66' thru 2" tb w/500 gal.  
15% acid, vac. all the way.

Acidized perf. 5037-43' w/1000 gal. 15%  
acid thru 2" tb. w/Lynes packer set @ 5027'  
& 5045', vac. all the way.

