

APR 17 1971

DRILLER'S LOG

WELL NAME Dillinger "A" No. 1 COMPANY OPERATING Anadarko Production Company
ADDRESS OF COMPANY Box 351 Liberal, Kansas 67901

WELL LOCATION 1/4 NE 1/4 SW 1/4
1900 Ft. North of South Line,
2030 Ft. East of West Line, Sec. 10, Twp. 31S, Rge. 18W, Comanche County, Kansas

DRILLING STARTED 3-3, 19 71, DRILLING COMPLETED 3-14, 19 71
WELL COMPLETED 3-24, 19 71, WELL CONNECTED _____, BPND

ELEVATION 2003.0 Ft. Ground Level CHARACTER of WELL (Oil, Gas, Dry Hole) 68 BOPD + 24 BWP
oil 79 MCF

MCF/GOR
miss

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION

Name	From	To	No. of Shots	Gallons Used	Kind Used
Mississippi	4979	4984	10	Acidized w/750	15% NE

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
3 5/8"	538'	400	NONE
4 1/2"	5009'	150	NONE
2 3/8"	4987'	SN @ 4970'	

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Surface Sand & Clay	0	200	<u>Log 1/4</u>		
Red Red	200	410			
Shale	410	1920	Chase	2440	
Lime & Shale	1920	2200	Winfield	2504	
Lime	2200	2590	Council Bluffs	2818	
Lime & Shale	2590	2815	Admiral	3298	
Lime	2815	4550	Walworth	3425	
Lime & Shale	4550	4757	Jafka	3701	
Lime	4757	4842	Hedden	4152	
Shale & Lime	4842	5010	By Union	4321	
TOTAL DEPTH	5010		JRC	4334	
			BRC	4754	
			msm	4808	
			cher	4898	
			miss	4954	

RESULTS OF INITIAL PRODUCTION TEST: In 4 hrs. swabbed 44 B. O.

DST (1) 4924.5006
4924.5006