


Show Drill Stem Tests,
Well Stimulation and
Production Tests

10-31-18w

Formation	Top	Bottom
Sand	0	35
Clay	35	60
Sand & Red Bed	60	620
Red Bed & Shale	620	1323
Shale	1323	1600
I & Shale	1600	2385
Shale & Lime	2385	4100
Lime & Shale	4100	4168
Lime	4168	4300
Shale	4300	4360
Lime	4360	4425
Lime & Shale	4425	4475
Lime	4475	5205
TOTAL DEPTH	5205	

DST #1, 4957 - 5004 (Miss) 10 minute preflow with poor blow, increasing to good. Tool open 40 minutes with gas to surface in 38 minutes, TSTM. Recovered 340' fluid (40' GCM, 120' O&GCM, 120' G&MCO, 60' GCO). ISIP 1379# (40), PFP 24-36#, FP 48-121#, FSIP 1137# (40).



LOG TOPS	DEPTH
CHASE	2452
WIN	2518
CO GR	2831
ADM	3314
WAB	3444
TOP	3697
HEEB	4168
BR LM	4341
LKC	4356
BKC	4776
MARM	4831
CHER	4923
MISS	4976
LTD	5200
RTD	5205

10-31-18w

10-31-18W

DEC 25 1972

DRILLER'S LOG

WELL NAME Dillinger "A" #2 COMPANY OPERATING Anadarko Production Company
ADDRESS OF COMPANY Box 351 Liberal, Kansas 67901

WELL LOCATION C 1/4 NW 1/4 SW 1/4
1980 Ft. North of South Line,
660 Ft. East of West Line, Sec. 10, Twp. 31S, Rge. 18W, Comanche County, Kansas

DRILLING STARTED 10/19, 19 71, DRILLING COMPLETED 11/2, 19 71
WELL COMPLETED 11-11, 19 71, WELL CONNECTED _____, 19 _____

ELEVATION 2095.0 Ft. Ground Level CHARACTER of WELL (Oil, Gas, Dry Hole) OIL

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
Miss	4985	4995	20	Acidized 750	15% NE
				Acidized 3000	Mod 202

RECEIVED
STATE CORPORATION COMMISSION
DEC 8 1971
CONSERVATION DIVISION
Wichita, Kansas

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8 5/8	525'	390	NONE
4 1/2	5200'	150	NONE
2 3/8	5001'	SN @ 4984'	NONE

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Sand	0	35	TOTAL DEPTH	5205	
Clay	35	60			
Sand & Red Bed	60	620			
Red Bed & Shale	620	1323			
Shale	1323	1600			
Lime & Shale	1600	2385			
Shale & Lime	2385	4100			
Lime & Shale	4100	4168			
Lime	4168	4300			
Shale	4300	4360			
Lime	4360	4425			
Lime & Shale	4425	4475			
Lime	4475	5205			

RECEIVED
STATE GEOLOGICAL SURVEY OF KANSAS
AUG 1972

RESULTS OF INITIAL PRODUCTION TEST: Swabbed 84 BF (17% Water) 6 hrs.