

MAY 1 1971

DRILLER'S LOG

WELL NAME Doig "A" No. 2 COMPANY OPERATING Anadarko Production Company
ADDRESS OF COMPANY Box 351 Liberal, Kansas 67901
WELL LOCATION C $\frac{1}{4}$ NE $\frac{1}{4}$ SE $\frac{1}{4}$
1980 Ft. North of South Line,
4597 Ft. East of West Line, Sec. 10, Twp. 31S, Rge. 18W, Comanche County, Kansas
DRILLING STARTED 2-8, 19 71, DRILLING COMPLETED 2-20, 19 71
WELL COMPLETED 3-20, 19 71, WELL CONNECTED _____, 19 _____
ELEVATION 2121.0 Ft. Ground Level CHARACTER OF WELL (Oil, Gas, Dry Hole) Oil Miss Sur. P-95 BOPD + 94 MCF6PD

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
Mississippi	5018	5026	16	Acidized w/750	Mod 202

CASING RECORD			
Size	Amount Set	Sacks of Cement	Amount Pulled
8 5/8"	509'	400	NONE
4 1/2"	5216'	150	NONE
2 3/8"	5030'	S.N. @ 5014'	NONE

FORMATION RECORD					
Formation	Top	Bottom	Formation	Top	Bottom
Surface Sand & Clay	0	235	Chase	2482	
Red Bed	235	385	Winfield	2547	
Shale	385	1318	Co. House	2861	
Lime & Shale	1318	2325	Admire	3343	
Lime	2325	4500	Walack	3470	
Lime & Shale	4500	4625	Jaseba	3718	
Lime	4625	4700	Heckman	4193	
Cherty Lime	4700	5197	Br. Lm.	4358	
Cherty & Lime	5197	5225	LKC	4372	
TOTAL DEPTH	5225		BKC	4797	
			Marmaton	4850	
			Chero	4997	
			Miss	4997	

RESULTS OF INITIAL PRODUCTION TEST: In 6 hrs. swabbed 40 B. O.

DST (1) 4972.4024 (Miss)