


KANSAS GEOLOGICAL SOCIETY
500 East Murdock
Lawrence, Kansas



10-31-18W
CSI NW

JUL 17 1971

DRILLER'S LOG

WELL NAME Myers "A" No. 3 COMPANY OPERATING Anadarko Production Company
ADDRESS OF COMPANY Box 351 Liberal, Kansas 67901

WELL LOCATION 1/4 SW 1/4 NW 1/4
3300 Ft. North of South Line,
735 Ft. East of West Line, Sec. 10, Twp. 31S, Rge. 18W, Comanche County, Kansas

DRILLING STARTED 5/16, 19 71, DRILLING COMPLETED 5/27, 19 71
WELL COMPLETED 6/5, 19 71, WELL CONNECTED _____, 19 _____

ELEVATION 2111.0 Ft. Ground Level CHARACTER of WELL (Oil, Gas, Dry Hole) OIL
*FLO 232 BOPD +
154 MCFGPD/71/24*

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
Mississippi	5000	5004	8	Acidized 750	Mod 202

CASING RECORD <i>DST #1 4965-5022</i>			
Size	Amount Set	Sacks of Cement	Amount Pulled
8 5/8	513'	400	NONE
4 1/2	5021'	150	NONE
2 3/8	4999'	SN @ 4981'	NONE

FORMATION RECORD <i>Log Jads</i>					
Formation	Top	Bottom	Formation	Top	Bottom
Sand	0	33	Chase	2464	
Sand & Shale	33	210	Winfield	2534	
Red Bed	210	514	Conrad Grove	2848	
Red Bed & Shale	514	880	Admire	3330	
Shale	880	1588	Wabash	3460	
Shale & Lime	1588	1990	Talpa	3709	
Lime & Shale	1990	2395	Bellevue	4183	
Lime	2395	4615	Br. Lime	4354	
Lime & Shale	4615	4760	Sanjour	4369	
Chert	4760	5005	BKC	4788	
Lime & Chert	5005	5022	Chert	4933	
TOTAL DEPTH	5022		Miss	4988	

RESULTS OF INITIAL PRODUCTION TEST: Flowed 84 BO in 3 3/4 hrs.