

JAN 24 1970

DRILLER'S LOG

11-E-18W
CSE NW

WELL NAME: Uhl "A" No. 1; COMPANY OPERATING: Anadarko Production Company
ADDRESS of COMPANY: Box 351 Liberal, Kansas 67901
WELL LOCATION: C - 1/4 SE 1/4 NW 1/4,
3300 ft. North of South line,
1830 ft. East of West line: Sec. 11, Twp. 31S, Rge. 18W, Comanche County, Kansas
DRILLING STARTED 7-6, 1969; DRILLING COMPLETED 7-21, 1969
WELL COMPLETED 9-14, 1969; WELL CONNECTED _____, 19____
ELEVATION: 2131.0 ft. Ground Level; CHARACTER OF WELL (Oil, Gas, or Dry Hole) Gas


OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
Mississippi	5014'	5023'	18	1500	Mod 202
Mississippi	5008'	5012'	8	1000	15% NE
				Frac W/20,000 gals. 3% gelled acid + 20,000#	
				20-40 Sand.	
Mississippi	5008'	5016'	16	500	15% NE

Note: Set retrievable packer @ 4990'. Squeezed Perfs. 5008' - 5012' & 5014' - 5023' W/100 sks common.

Size	Amount Set	Sacks of Cement	Amount Pulled
8 5/8"	1069	600	None
4 1/2"	5192	160	None
2 3/8"	5004	SN @ 4988'	

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Surface Clay	0	30'	Total Depth	5195'	
Sand	30'	250'			
Red Bed	250'	391'			
Red Bed & Shale	391'	1045'			
Shale & Anhydrite	1045'	1070'			
Red Bed & Shale	1070'	1610'			
Shale & Shells	1610'	1750'			
Anhydrite & Salt	1750'	2060'			
Shale	2060'	2250'			
Shale & Lime	2250'	4402'			
Lime	4402'	4518'			
Lime & Shale	4518'	4620'			
Lime	4620'	5195'			



RESULTS of INITIAL PRODUCTION TEST: On 72 hr. 1-Point test taken 9-22-69 - gas gauged
755 MCFD.