

KANSAS DRILLERS LOG

WICHITA BRANCH

S. 26 T. 31S R. 18 ^E/_W
 Loc. 520' FNL & 535' FEL
 County Comanche

API No. 15 — 033 — 20,204
 County Number

Operator
Texas Oil & Gas Corp.

Address
200 West Douglas, Suite 300


Well No. #1 Lease Name Boisseau

Footage Location
520' feet from (N) (S) line 535' feet from (E) (W) line

Principal Contractor Xplor Drilling Co. Geologist High Plains Consulting Ltd.

Spud Date 7-12-76 Total Depth 5132' P.B.T.D. 5123'

Date Completed 9-13-76 Oil Purchaser Koch



Locate well correctly
 Elev.: Gr. 2130'
 DF 2135' KB 2138'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	497'	Class "H" Lite-weight	200 300	2% Gel, 3% CaCl ₂
Production	7 7/8"	4 1/2"	10.5#	5131'	Common	125	2% Gel 3% CaCl ₂

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A	4 JSPF	Deep Penet.	5090-5106'

Size	Setting depth	Packer set at
2 3/8"	5116' K.B.	N/A

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidize w/4500 gallons acid.	5090-5106'

INITIAL PRODUCTION

Date of first production <u>9-8-76</u>	Producing method (flowing, pumping, gas lift, etc.) <u>Pumping</u>			
RATE OF PRODUCTION PER 24 HOURS	Oil <u>24</u> bbls.	Gas <u>N/A</u> MCF	Water <u>0</u> bbls.	Gas-oil ratio <u>N/A</u> CFPB
Disposition of gas (vented, used on lease or sold) <u>N/A</u>		Producing interval (s) <u>5090-5106'</u>		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
Texas Oil & Gas Corp.

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. #1 Lease Name Boisseau Oil Well

S 26 T 31S R 18 E


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1, 5086-5113', (Mississippi) w/results as follows: IFP/30": 77-73#, GTS 5", 78 MCFD. ISIP/75": 1528#. FFP/90": 75-99#, stable @ 38 MCFD. FSIP/225": 1525#. Rec 355' heavily O&GCM.				
Herrington	2526	-388		
Winfield	2588	-450		
Towanda	2652	-514		
Fort Riley	2706	-568		
Wreford	2860	-722		
Bader	2992	-854		
Cottonwood	3085	-947		
Red Eagle	3172	-1034		
Indian Cave	3342	-1204		
Woodsiding	3394	-1256		
Stotler	3542	-1404		
Topeka	3806	-1668		
Lecompton	4026	-1888		
Queen Hill	4084	-1946		
Heebner	4272	-2134		
Douglas	4316	-2178		
Souglas Sand	4341	-2203		
Iatan	4431	-2293		
Lansing	4462	-2324		
Cherryvale	4738	-2600		
Swope	4806	-2674		
B/Kansas City	4894	-2756		
Marmaton	4946	-2808		
Cherokee	5037	-2899		
Mississippi	5094	-2956		
RTD	5132	-2994		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	
	Harold A. Brown Signature District Geologist Title
	10-12-76 Date