

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY  
412 Union National Bldg., Wichita, Kansas


25-31-18W  
27

Company - HARBAR DRIG. CO.  
Farm - Boisseau No. 1.

SEC. 27 T. 31 R. 18 W  
CSE NW

Total Depth. 6008  
Comm. 11-22-44 Comp. 3-31-45  
Shot or Treated.  
Contractor.  
Issued. 6-9-45

County. Comanche  
KANSAS



CASING:  
13" 294' Cem.

Elevation. \_\_\_\_\_

Production. Dry

Figures Indicate Bottom of Formations.

surface clay	0-40	smooth	5030
sand	245	slightly rough	5040
shale & shells	300	lime & shale	5077
red rock shells	490	lime	5109
shells & shale	875	lime & shale	5115
shale & lime shells	1040	Miss. lime (Drill	
lime & shells	1080	stem test)	5147
anhydrite	1105	lime	5214
shale & shells	1445	lime & cherty	
shale	1550	streaks	5230
shale & shells	1630	lime	5255
shale - lime	1730	lime & chert	5294
lime shells & shale	1820	lime hrd	5342
lime & shells	1905	lime chert	5350
lime - shale	1995	Reaming 12 1/2" hole from	
lime	2185	297 - 1987	
shale	2215	lime	5445
lime shells	2360?	lime & shale	5460
lime - shale	2360?	lime	5525
lime	2410	lime & shale	5536
lime - shale	2515	lime cherty	5541
lime pyrite	2545	lime	5548
lime	2815	lime hrd cherty	5558
R. lime	2830	chert	5561
lime & shale	2905	lime cherty	5589
lime H.	2925	lime	5686
broken	2935	lime & chert	5719
lime H.	2940	lime	5835
lime	3100	lime shale	5841
lime - shale	3180	lime	5880
lime	3275	something hard	5881
lime - shale	3320	lime	5887
lime	3515	lime sdy	5894
lime shells & shale	3555	lime	5910
lime	3625	shale & sand	5917
shale	3650	lime	5927
lime & shale	3670	lime & shale	5963
pyrite	3680	shale & sand shale	5970
lime	3840	lime	6008
lime med.	3856	Total Depth	
soft	3866		
lime H.	3870	Tops:	
<del>lime med.</del>	3985	Lansing-K. C.	4456-5125
shale & lime	4105	Miss.	5115-5425
lime	4270	Kinderhook	5425-5475
lime hrd	4280	Maquokata	5475-5535
lime	4340	Cherty Viola	5535-5611
hard	4350	Viola Dolo.	5611-5809
medium	4365	Simpson	5809-5966
soft	4380	Arbuckle Dolo.	5966-6000
medium	4400		
hard	4410		
lime hrd	4445		
lime	4868		
shale	4875		
lime	4990		
lime & shale - rough	5020		