

AFFIDAVIT AND COMPLETION FORM

ACO-1

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.

OPERATOR Holt Oil & Gas Corporation API NO. 191-21,355
 ADDRESS 8150 N. Central Expwy., #1255 COUNTY Sumner
Dallas, TX 75206 FIELD Not Assigned

**CONTACT PERSON Bryan W. Beliew LEASE Zeka
 PHONE _____

PURCHASER _____ WELL NO. #1
 ADDRESS _____ WELL LOCATION SE NW NE

DRILLING CONTRACTOR Range Drilling Co. 990 Ft. from FNL Line and
240 Page Ct., 220 W. Douglas 1650 Ft. from FEL Line of
Wichita, KS 67202 the SEC. 1 TWP. 31S RGE. 2E West

PLUGGING CONTRACTOR Range Drilling Co.


ADDRESS _____

TOTAL DEPTH 3,775' PBTD _____

SPUD DATE 1-23-82 DATE COMPLETED 1-30-82

ELEV: GR1303 DF _____ KB 1311

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS
 Report of all strings set — surface, intermediate, production, etc. (New) / (Used) casing.



WELL PLAT
 (Quarter) or (Full) Section - Please indicate.

KCC _____
 KGS

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	23#	453	Class "A"	320	3% CaCl

TEST DATE: _____ PRODUCTION _____

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	A.P.I. Gravity
RATE OF PRODUCTION PER 24 HOURS	Gas MCF	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval(s)	

** The person who can be reached by phone regarding any questions concerning this information.
 A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

RECEIVED
 STATE CORPORATION COMMISSION

FEB 25 1982

Name of Well fresh water producing stratum _____ Depth _____
 Estimated height of cement behind pipe _____

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand and Shale	0	455		
Shale	455	720		
Shale w/ Lime	720	1,575		
Shale	1,575	1,694		
Lime/Shale	1,694	2,140		
Shale	2,140	2,677		
Shale and Lime	2,677	3,360		
Lime	3,360	3,508	Kansas City	
Shale and Lime	3,508	3,724		
Lime	3,724	3,737	Mississippi	
Shale and Lime	3,737	3,775		
T.D.	3,775			

DST #1 - 3,721'-3,739' - IFP 10 min;
 ISIP 39 min; FFP 30 min; FSIP 33 min;
 IHP 1,856; IFP 64 psi; ISIP 957 psi;
 FFP 84 psi; FSIP 597 psi; FHP 1,856;
 recovered 65' mud.

DST #2 - 3,108'-3,150' - IFP 30 min;
 ISIP 30 min; FFP 30 min; FSIP 33 min;
 IHP 1,506; IFP 55 psi; ISIP 1,044 psi;
 FFP 73 psi; FSIP 1,008 psi; FHP 1,498
 recovered 70' mud.

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

A F F I D A V I T

STATE OF Texas, COUNTY OF Dallas SS,

Bryan W. Bellew OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:

MY COMMISSION EXPIRES: 10-6-84

1-31-2W

State Geological Survey
WICHITA BRANCH

Well Log
#1 Zeka
SE NW NE
Section 1-31S-2W
Sumner County, Kansas

Operator: Holt Oil & Gas
8150 N. Central Expressway #1255
Dallas, Texas 75206


Casing Record: 8-5/8 @ 453' w/320 sx cement

Date Completed: 1-30-82

<u>From</u>	<u>To</u>	
0	455	Sand and shale
455	720	Shale
720	1575	Shale w/lime
1575	1694	Shale
1694	2140	Lime/shale
2140	2677	Shale
2677	3360	Shale and lime
3360	3508	KC/lime
3508	3724	Shale and lime
3724	3737	Mississippian
3737	3775	Shale and lime
3775	RTD	

State of Kansas
County of Sedgwick

Gary L. Reed, Vice President of Range Drilling Company, Inc., being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct.


Gary L. Reed

SUBSCRIBED AND SWORN TO before me this 4th day of February, 1982


Notary Public

My commission expires

