

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOG

IMPORTANT
Kans. Geo. Survey request
samples on this well.

State Geological Survey
WICHITA BRANCH


API No. 15 — 191 — 21,076
County Number

S. 10 T. 31 R. 2 K W

Loc. NW NW SE

County Sumner

640 Acres
N



Locate well correctly

Elev.: Gr. 1279

DF KB 1284

Operator

Rains & Williamson Oil Co., Inc.

Address

435 Page Court Wichita, Kansas 67202

Well No.

#1

Lease Name

Dennison

Footage Location

feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

Silverado Drilling, Inc.

Geologist

Mike D. Engelbrecht

Spud Date

3-25-81

Date Completed

4-5-81

Total Depth

4196'

P.B.T.D.

Directional Deviation

Oil and/or Gas Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
	12 1/4"	8 5/8"		410'	Common	300 sx.	2% cc., 1/4# flocele

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF		bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Rains & Williamson Oil Co., Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Dry Hole

Well No.

#1

Lease Name

Dennison

S 10 T 31 S R 2 E W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

DST #1 - 3227-3248, 30 (30) 60 (30).

Rec. 15' SO&GCMW, 560' SGCSW.

FP's 50-180, 220-295. IBHP 1055,

FBHP 1025. Temp. 112°.

DST #2 - 4178-4191, 30 (30) 60 (60).

Rec. 60' mud. FP's 49-49, 49-49.

IBHP 57, FBHP 57. Temp. 112°.

DST #3 - 3168-4196, 30 (30) 60 (60).

Rec. 660' water and gas cut mud.

540' water. FP's 68-298, 344-594.

IBHP 1486, FBHP 1486. Temp. 119°.

SAMPLE TOPS

Elmont	1747 (-463)
White Cloud	1927 (-643)
Heebner	2480 (-1196)
KC	3107 (-1823)
Erros. Miss	3768 (-2484)
Miss. Lime	3780 (-2496)
Kinderhook	4126 (-2842)
Simpson Sd.	4188 (-2904)
RTD	4196 (-2912)

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Wilson Rains

Signature

President

Title

4-27-81

Date