

13-31-2W Ind
PT

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

F Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

C Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 5420 EXPIRATION DATE 6-30-83

OPERATOR White & Ellis Drilling, Inc. API NO. 15-191-21,511

ADDRESS 401 E. Douglas - Suite 500 COUNTY Sumner
Wichita, Kansas 67202 FIELD

** CONTACT PERSON Mike Dixon PROD. FORMATION
PHONE (316) 263-1102

PURCHASER N/A LEASE Renn

ADDRESS WELL NO. 1

DRILLING White & Ellis Drilling, Inc. WELL LOCATION S/2 NE NW

CONTRACTOR 401 E. Douglas - Suite 500 660 Ft. from East Line and

ADDRESS 401 E. Douglas - Suite 500 990 Ft. from North Line of
Wichita, Kansas 67202 the NW (Qtr.) SEC13 TWP31S RGE 2 (W).

PLUGGING White & Ellis Drilling, Inc. WELL PLAT (Office Use Only)

CONTRACTOR 401 E. Douglas - Suite 500

ADDRESS 401 E. Douglas - Suite 500

Wichita, Kansas 67202

TOTAL DEPTH 3788' PBSD

SPUD DATE 12-23-82 DATE COMPLETED 1-5-83

ELEV: GR 1294 DF KB 1299

DRILLED WITH ~~CABLE~~ (ROTARY) ~~AIR~~ TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

Amount of surface pipe set and cemented 481' DV Tool Used? _____

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - ~~Oil or Gas~~, Dry, ~~Injection~~, ~~Temporarily Abandoned~~, ~~Owner~~

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.


A F F I D A V I T

_____ Micheal W. Dixon, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

Micheal W. Dixon
Micheal W. Dixon (Name)

State Geological Survey
WICHITA BRANCH



(Office Use Only)
KCC
KGS
SWD/REP _____
PLG. _____

PZ

FILL IN WELL INFORMATION AS REQUIRED:

WELL NO. 1

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Check if no Drill Stem Tests Run.				
IATAN	2793	-1494		
KC	3103	-1804		
B/KC	3373	-2074		
CHEROKEE	3618	-2319		
MISS	3771	-2472		
RTD	3788			
DST #1: 3773'-82', 30-45-60-60, Rec. 125' M w/ V Few Spks of Oil and 150' SW IFP 20-75 FFP 130-150 ISIP 1435 FSIP 1425				
If additional space is needed use Page 2, Side 2				

Report of all strings set— surface, intermediate, production, etc. **CASING RECORD** (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"		481'	common	250	3% CC


LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at



13-31-2W Ind IT

WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: White & Ellis Drilling, Inc. 401 E. Douglas - Suite 500 Wichita, Kansas 67202

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500, Wichita, Ks. 67202

Lease Name Renn Well No. #1

Sec. 13 T. 31S R. 2W Spot S/2 NE NW

County Sumner State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 481' with 250 sx. 3%cc

Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 3788'

Drilling Commenced 12-26-82 Drilling Completed 1-5-82

Formation	From	To	Tops
Cellar	0	7	Anhydrite 500
Sand, Shale	7	600	Stalnaker 2797
Shale	600	626	Kansas City 3124
Sand, Shale	626	1185	Mississippi 3770
Lime, Shale	1185	1408	
Shale, Sand	1408	1887	
Shale, Lime	1887	2079	
Sand, Shale	2079	2169	
Shale, Lime	2169	2381	
Lime, Shale	2381	2530	
Shale, Lime	2530	2797	
Sand	2797	2850	
Shale, Sand, Lime	2850	2973	
Shale, Lime	2973	3124	
Lime	3124	3450	
Shale, Lime	3450	3623	
Lime, Shale	3623	3691	
Shale, Lime	3691	3770	
Lime	3770	3788	

State Geological Survey
WICHITA BRANCH