

34-31-2W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- GULF OIL CORP
Farm- Fuqua No. 1

SEC. 34 T. 31 R. 2W
SW SE NE

Total Depth. 4238'
Comm. 4-28-58 Comp. 5-29-58
Shot or Treated.
Contractor. Barnett Drlg.
Issued. 12-3-60

County Sumner
KANSAS



CASING:
8 5/8" 428' cem w/350 sx.
4 1/2" 2100' cem w/200 sx.

Elevation. 1250' RB

Production. 2,887,000 CFG

Figures Indicate Bottom of Formations.

surface	15
shale & shells	305
gray shale	380
shale	420
Anhydrite	465
shale	485
lime	640
shale & lime	1710
shale	1910
shale & lime	2125
shale	2140
lime	2240
lime & shale	2550
shale	2680
lime & shale	2775
shale	2835
sand & shale	2980
shale	3120
lime	3450
lime & shale	3520
lime	3720
shale & lime	3760
lime	4200
lime & shale	4235
sand	4238
Total Depth	

TOPS: SCOUT	
Anhydrite	420
Howard	1935
Topeka	2055
Douglas Shale	2576
Kansas City	3130
Base Kansas City	3395
Marmaton	3458
Mississippi	3800
Kinderhook	4159
Chatt.	4202
Simpson	4226