

State Kansas County Comanche

Company Grahamhart-Miller Oil Co. Well No. 1

Farm Kennedy "A"

Survey _____

Block No. _____ Sec. 2 Twp. 31S Range 17W

Co-Ord. C.P. 4200 Elev. 2110 KB

Ctr NE NE

(Graham-Michaelis) 2104 Gr
 25%-Grahamhart-Miller Oil Co.
 35%-Newmont Oil Co.
 35%-Cyprus Oil Co.
 5%-E. M. Voorhees
 DHM: Carter Oil Co. - \$5000
 Gulf - \$7000 (pd only half)
 Acreage: Magnolia Petr. Co.

Geol: Walter Martz

NOTE: Show Sketch of Lease and Well Location in Above Space

660 Ft. from N. Line Ft. from S. Line

Ft. from W. Line 660 Ft. from E. Line

Date	Depth	SPD 6-5-56
<u>5-31-56</u>		Location staked. Building road
<u>6-1</u>		Digging pits
<u>6-5</u>		MIRT
<u>6-6</u>	<u>300</u>	Drlg 12 $\frac{1}{4}$ " hole to 309. Then rat hole ahead to 900.
<u>6-7</u>	<u>975</u>	Rat holed ahead.
		8 5/8" @ 300' w/200 sx cem, 7 gal, 7 c.c. PD 7:10 pm 6-6-56
<u>6-8</u>		D.P. and are going to bottom.

Date	Depth	
6-9	2225	Drlg
6-11	2820	Drlg
6-12	3150	Drlg
6-13	3570	Making trip ($1\frac{1}{2}^{\circ}$ off)
6-14	3775	Down for repair. Drlg motor.
6-15	3909	Drlg ($1\frac{1}{2}^{\circ}$ @ 3775) Started up late last night.
6-16	4103	Drlg
6-18	4173	Heebner (-2063)
	4188	Toronto (-2078)
	4209	Douglas Group (-2099)
	4344	Brown Line (-2234)
	4356	Lansing-K.C. (-2246)
	4457	Drlg
6-19	4583	Drlg. Lost cir 4561. Have not regained completely.
6-20	4694	Drlg (Still losing some mud)
6-21	4805	Drlg
6-22	4751	B/KC (-2641)
	4774	Marmaton (-2664)
	4894	Cherokee (-2784)
	4954	Cher. Sd (-2844)
	4972	Miss (-2862)
	4975	Ready to DST 4938-75.

808069

State Kansas County Comanche

Company Grahamart-Miller Oil Co. Well No. 1

Farm Kennedy "A"

Survey _____

Block No. _____ Sec. 2 Twp. 31S Range 17W

Co-Ord. _____ Elev. 2110 KB

CTR NE NE

Page 2

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
6-23	DST #1 4938-75, op 60", cl 30". Gas in 1". In 10" 648,000; 20" 734,000; 30" 768,000, 45" 734,000 and in 60" 734,000. Rec 125' sgem. IF & FF-270#, BHP-1670#.	
	4975	Drig.
6-25-56	DST #2 4978-95, op 1 hr, cl 30". Gas in 22". In 30" 62,000; in 45" 44,000 and 1 hr too small to meas.	

Date	Depth	
		Rec 30' sli gem. IF&FF-50, BHP-1680#.
		DST #3 4995-5025, op 1 hr, cl 30". Gas in 4". In 10" 481,000, 20" 560,000, 30" 560,000, 45" 537,000 and in 60" 496,000. Rec 90' wtry mod, 240' mdy SW. IF-210, FF- 240, BHP-1500#
	5025	T.D. Coming out hole w/log. Log went to only 4840. To re- condition hole & go back w/log
6-26	5025	Finished log 6 a.m. Getting ready to d.d.
6-27	5111	T.D. DST #4 (Straddle packer) 5024-51, op 1 hr, cl 30". Rec 180' gas, 1100' vsc&gcsw. IF-200, FF-600, BHP-1600 Waiting on orders.
6-28	5134	R.T.D. D&A (Plugging compl. 6-28-56.)
Log Tops:		
		Heebner 4174 (-2064)
		Brn. Lime 4345 (-2235)
		Lansing-K.C. 4361 (-2251)
		B/K.C. 4753 (-2643)
		Marmaton (?) 4775 (-2665)
		Cher 4896(-2786) Cher sd 4955(-2845)
		Miss. 4970 (-2860)

828069