

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company GULF OIL CORPORATION
Farm M. A. Lorimor No. 1

SEC. 36 T. 31 R. 20W
CSE SW

Total Depth. 5239' PB 6365'
Comm. 7-11-47 Comp. 2-17-48
Shot or Treated. Acidized
Contractor.
Issued. 3-13-48

County. Comanche

KANSAS



Elevation. 2104 ft.

Production. Dry

CASING:

13-3/8" 222' Cem. w/250 SX
8-5/8" 2450' Cem. w/200 SX
5-1/2" 5194' Cem. w/150 SX

Figures Indicate Bottom of Formations.

sand	0-65
shale & red bed	225
shale & shells	995
shale & lime	1565
shale & shells	1745
shale & lime	2040
shale & shells	2325
shale & lime	2400
lime	2735
lime & shale	2810
lime	2970
lime & shale	3130
shale	3360
shale & lime	3435
lime	3795
lime & shale	3880
shale	3975
lime	4370
lime & shale	4515
lime	4837
shale	4850
lime	5150
lime & shale	5180
lime	5940
lime & chert	5950
lime	5980
lime & chert	6020
lime	6235
sand	6270
sand & shale	6305
lime	6365
Total Depth	

Tops:

Cimarron Anhydrite	1115
Wellington Group	1690
Wellington Salt	1890
Base Salt	2310
Fort Riley	2364

Shelby	2750
Wesford	2840
Bea	3130
Lansing	4510
Mississippi Lime	5191
Chattanooga Misener	5980
Viola	5988
Simpson	6146
Arbuckle	6306

Shot w/85 qts. 5207-37

Acid. w/2000 gals. 9-27-47

" w/6000 gals. 9-30-47

" w/ 500 gals. 10-14-47

" w/1000 gals. 10-16-47

" w/2000 gals. 10-19-47

" w/2000 gals. 1-13-48

Perforated w/16 holes 5191-94'

Top collar on 5 1/2" 13' below rotary table.