

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


3-31-21W

Company- RUPP-FERGUSON
Farm- Yeoman No. 1

SEC. 3 T. 31 R. 21W
CS/2 SE

Total Depth. 5237'
Comm. 2-13-56 Comp. 3-7-56
Shot or Treated.
Contractor. Rupp-Ferguson Oil
Issued. 6-16-56

County Clark
KANSAS



Elevation. 2236' RB

Production. 24,000,000 CFG

CASING:

20" 104' cem w/200 sx
13 3/8" 380' cem w/400 sx
5 1/2" 5231' cem w/100 sx

Figures indicate Bottom of Formations.

sand	85
shale	127
sand, shale, red bed	168
red bed	310
sand & gravel	348
red bed & shale	400
anhydrite	420
shale & shells	600
salt & shale	1010
red bed, shale, shells	1250
shale & shells	2405
lime & shale	2545
lime	2720
lime & shale	2800
lime	2830
lime & shale	3085
lime	3160
lime & shale	3830
lime	4095
lime & shale	4325
lime, shale, sand	4427
shale & sand	4493
lime & shale	4534
lime	4816
lime & shale	4864
lime	4890
lime, shale streaks	4945
lime & shale	5000
lime	5130
lime & shale	5162
Core #1	5201
Core #2	5231
Core #3	5237
Total Depth	

Tops: Scout	
Heebner	4282
Brown Lime	4461
Lansing	4487

Base Kansas City	4936
Marmaton	4953
Ft. Scott	5026
Cherokee	5079
Mississippi	5178