

## Q\ KANSAS


WELL COMPLETION REPORT AND  
DRILLER'S LOGAPI No. 15 — 025 — 20,494  
County NumberState Geological Survey  
WICHITA BRANCHS. 4 T. 31 R. 21 E  
W

Loc. C NW NW

County Clark

640 Acres

N



Locate well correctly

Elev.: Gr. 2263

DF 2270 KB 2270

## Operator

Imperial Oil Company

## Address

720 Fourth Financial Center, Wichita, Kansas 67202

## Well No.

2-4

## Lease Name

MARTIN

## Footage Location

660 feet from (N) (X) line

660 feet from (X) (W) line

## Principal Contractor

Ramco Drilling Corp.

## Geologist

Rene Stucky

## Spud Date

8/12/81

## Date Completed

8/24/81

## Total Depth

RTD 5325'

## P.B.T.D.

## Directional Deviation

NA

## Oil and/or Gas Purchaser

## CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 $\frac{1}{2}$ "	8 5/8"	24#	774'	Common Lite	200 100	3% CC 3% CC

## LINER RECORD

## PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

## TUBING RECORD

Size	Setting depth	Packer set at

## ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used		Depth interval treated

## INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)				
RATE OF PRODUCTION PER 24 HOURS	Oil bbis.	Gas MCF	Water bbis.	Gas-oil ratio CFPB	Producing interval(s)	
Disposition of gas (vented, used on lease or sold)						

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Driller's Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Driller's Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Imperial Oil Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.		
Well No. 2-4	Lease Name MARTIN	Dry Hole		
S 4 T 31 R 21 E W	Clark			
<b>WELL LOG</b>				
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.				
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 5119-5202' 30/30/30/30 Rec. 10' DM IFP: 62-82# ISIP: 103# FFP: 82-82# FSIP: 93#			E-Log Tops	
DST #2 5195-5235' 30/30/30/30 Rec. 10' mud IFP: 52-52# ISIP: 62# FFP: 52-52# FSIP: 62#			Heebner	4290 (-2020)
DST #3 5234-64' 30/30/30/30 Rec. 5' mud IFP: 41-41# ISIP: 93# FFP: 41-41# FSIP: 93#			Brown Lime	4478 (-2208)
DST #4 5300-25' 30/30/30/30 Rec. 15' mud IFP: 31-41# ISIP: 206# FFP: 41-51# FSIP: 134#			Lansing	4500 (-2230)
			B/KC	4950 (-2680)
			Marmaton	4964 (-2694)
			Cherokee	5097 (-2827)
			Inola	5185 (-2915)
			Morrow	5192 (-2922)
			Mississippi	5196 (-2926)
			LTD	5317 (-3047)
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				
Date Received	 Signature Attorney-in-Fact Title September 14, 1981 Date			