

KANSAS DRILLERS LOG


DEC 11 1975

API No. 15 — 025 — 20,096
County Number

AMA. PROD.

S. 1 T. 31 R. 22 E
Loc. 510' FNL & 510' FEL
County Clark

Operator Mesa Petroleum Company	
Address Box 2009 Amarillo, Texas 79105	
Well No. #1-1	Lease Name Dailey DAILY
Footage Location 510 feet from N. line 510 feet from (E) line	
Principal Contractor Gabbert-Jones Drilling Co.	Geologist Dave Ward
Spud Date 1/2/76	Total Depth 5750'
Date Completed 1/23/76	P.B.T.D.
Oil Purchaser Undetermined	



Locate well correctly
Elev.: Gr. 2242.2'
DF 2245' KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	603'	Dowell lite "H"	225 150	4% gel, 2% CaCl 3% CaCl
Production	7-7/8"	4-1/2"	10.5#	5360'	Litepoz 3	190	2% gel, 10% salt, 1/2%D-59, 12#gil/sx

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4		5199-5208'
TUBING RECORD					
Size	Setting depth	Packer set at			
2-3/8"	5138'	5138'			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
None	

INITIAL PRODUCTION

Date of first production 1/30/76	Producing method (flowing, pumping, gas lift, etc.) Flowing (4 Pt Test)		
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas CAOF 47,000 MCF	Water bbls.
Disposition of gas (vented, used on lease or sold) Vented	Gas-oil ratio 753,000 CFPB		
Producing interval (s) 5199-5208'			

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044. XC: KGS, Denver Office

Operator

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Mesa Petroleum Co.

Well No.

1-1

Lease Name

Dailey

Gas

S 1 T31S R22 E4
W

Clark County, Kansas

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP


BOTTOM

NAME

DEPTH

SEE ATTACHED DRILLERS LOG

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



S.E. Dobler

Signature

Drilling & Production Supervisor

Title

2-3-76

Date

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

RECEIVED

1-31-22W

JAN 29 1976

1-1 Dailey
470' FEL & 330' FNL Sec 1-31S-22W
Clark County Kansas

AMA. PROD.

Commenced: 1-2-76

Completed: 1-20-76

OPERATOR:

Depth		Formation	Remarks
From	To		
0	516	Shale=Sand-Redbed	Ran 15 jts of New 20#
516	1200	Redbed	8 5/8" csg set @ 604' Cemented
1200	1900	Shale-Sand	w/230 sks L.W. 4% Gel 2% CC
1900	2575	Shale-Lime	+ 150 sks Regular 3% CC
2575	5035	Lime-Shale	PD @ 10:30 p.m. 1-3-76
5035	5145	Lime	
5145	5333	Lime-Shale	
5333	5750	Lime	
5750 - TD			Ran 135 jts of 4 1/2" csg set @ 5360' Cemented w/190 sks 50/50 Posmix 2% Gel - 10% Salt PD @ 7:00 p.m. 1-20-76


I, James S. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled 470' FEL & 330' FNL, Sec 1-31S-22W, Clark County, Kansas, to the best of my knowledge and belief.


JAMES S. SUTTON II

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State on this 27th day of January, 1976, personally appeared James S. Sutton, II, who personally known to be the identical person who executed the within and foregoing instrument, and acknowledged to me that he executed the same as his free and voluntary act and for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.


ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission Expires: February 6, 1979.

