

3-31-26W

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY BURK ROYALTY CO.

SEC. 3 T. 31 R. 26W

FARM Cherry

NO. 1

LOC. C NW SW

TOTAL DEPTH 5750'

COMM. 8-28-64

COMP. 9-14-65

SHOT OR TREATED

CONTRACTOR Wagner-Wyant

ISSUED 9-3-66

CASING

20

10

15

8 5/8" 1538'

12


6

13

5 1/2" 5042'

COUNTY Meade

KANSAS



ELEVATION 2571' KB

PRODUCTION 2950 MCFGPD SIP
 1300#; BTU 952; (Lans 4522-26)
 2100 MCFGPD SIP 1405# BTU
 1053; (KC 4882-86)

FIGURES INDICATE BOTTOM OF FORMATIONS

0-305	Sand and Surface Clay
305-370	Sand and Clay
370-800	Red Bed Gyp.
800-1296	Shale & Gyp. & Anhy.
1296-1433	Red Bed, Shale, & Anhy.
1433-1538	Red Beds
1538-1598	Anhy. & Shale
1598-2288	Shale & Anhy.
2288-2548	Shale & Anhy.
2548-2645	Anhy. & Shale
2645-2880	Shale & Anhy.
2880-2970	Shale & Anhy.
2970-3079	Lime & Shale
3079-3249	Lime & Shale
3249-3365	Lime & Shale
3365-3575	Lime & Shale
3575-3786	Shale & Lime
3786-3980	Shale & Lime
3980-4050	Lime & Shale
4050-4245	Lime & Shale
4245-4333	Lime & Shale
4333-4435	Lime & Shale
4435-4550	Lime
4550-4580	Lansing Test Interval
4580-4708	Lime
4708-4760	Lime
4760-4855	Lime & Shale
4855-4905	Lime
4905-4960	Kansas City Test Interval
4960-5033	Lime & Chert
5033-5080	Lime
5080-5165	Lime
5165-5206	Lime
5206-5285	Lime
5285-5318	Lime
5318-5391	Lime
5391-5420	Lime

5420-5476	Lime
5478-5509	Lime
5509-5564	Lime
5564-5566	Lime
5566-5589	St. Louis Test Interval
5589-5629	Lime & Chert
5629-5663	Lime
5663-5705	Lime
5705-5747	Lime
5747-5750	Lime
5750	TD

TOPS: SCOUT	
Herrington	2660
Upper Krider	2684
Lower Krider	2718
Winfield	2766
Gage	2806
Upper Fort Riley	2833
Lower Fort Riley	2886
Wreford	2943
Council Grove	2977
Pennington	3643
Heebner	4340
Toronto	4366
Lansing "A"	4520
Kansas City	4880
Marmaton	5026
Cherokee	5164
Mississippi St. Genevieve	5360
St. Louis	5423
Spergen	5614