

KANSAS DRILLERS LOG

API No. 15 — County — Number —

Operator

Texas Oil & Gas Corp.

Address

200 West Douglas, Suite 300, Wichita, Kansas 67202

Well No.

#1

Lease Name

Lang "A"

Footage Location

1320 feet from (N) (S) line 990 feet from (E) (W) line

Principal Contractor

Xplor Drilling Co.

Geologist

Robert L. Laymon

Spud Date

3-12-79

Total Depth

5050'

P.B.T.D.

4912'

Date Completed

5-27-79


Oil Purchaser

N/A

S. 4 T. 31S R. 26 E W

Loc. 1320' FNL & 990' FEL

County Meade County, Kansas

640 Acres
N

Locate well correctly

Elev.: Gr. 2542'

DF — KB 2552'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		13-3/8"		40'		30	
Intermediate		8-5/8"		1158'		600	
Production		4-1/2"		4972'		200	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A	2 JSPF	N/A	4870-74'
TUBING RECORD			2 JSPF	N/A	4870-74'
Size	Setting depth	Packer set at			
2-3/8"	N/A	4753'			
2-3/8"	N/A	4806'			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
250 gallons acetic acid	4870-74'
Acidized w/500 gallons 15% MSR	4870-74'

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
P & A		N/A			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	N/A bbls.	N/A MCF	N/A bbls.	N/A	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		
N/A			N/A		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Texas Oil & Gas Corp.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. #1	Lease Name Lang "A"	Dry Hole
S <u>4</u> T <u>31</u> S R <u>26</u> ^E _(W)		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Heebner	4335	-1783		
Iatan	4463	-1911		
Lansing	4483	-1931		
Wyandotte	4619	-2067		
Iola	4708	-2156		
Dennis	4770	-2218		
Swope	4868	-2316		
Hertha	4938	-2386		
B/Kansas City	4987	-2435		
Marmaton	5009	-2457		
TD	5050			
PBTD	4912			
NO DST's.				
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				

Date Received	 HAROLD A. BROWN District Geologist May 29, 1979
	Signature Title Date