

11-95W

MAP NO.

K-85

WILDCAT

3-31S-26W

STATE Kans COUNTY Meade

150' SEC 58' CNW SW

OPER. Burk Royalty Co. - Wichita Falls, Texas FT/FR _____ LINE _____WELL 1 FARM Cherry (6000' Miss Test) FT/FR _____ LINE _____L WC ELEV. 2561 2569 DF 2571 KB _____CONT. Wagner-Wyant Drlg. GEOL. Ralph ReynoldsCO. Mack Oil - Support, North. Nat. Gas - SupportF.R. 8-24-64 SPUD 8-29-64 COMP. 11-3-64TD 5750 FM. Sperg PBTD. DUAL COMPLETION

Completion Record	PRODUCING FM.	FROM	TO	PERF W/HOLES	TREATMENT
	<u>Lans</u>	<u>4532-36</u>	<u>9</u>	<u>1250A</u>	
	<u>KC</u>	<u>4892-96</u>	<u>12</u>	<u>500A</u>	
	<u>COF 2,950,000 Cfgpd (Lans) - COF 2,100,000 Cfgpd (KC)</u>				
Casing Record	<u>WC-15 mi N of McKinney (Mrw-Miss) Gas Field</u>				
	<u>8 5/8" @1538 w/750 sx. 5 1/2" @5041 w/150 sx.</u>				

5.4

★

Data Inc.

(KB Log)		<u>DST #1 (Lans) 4530-50, Op 2 hrs, GTS/</u>
Hb	4345 -1774	6", Ga 1,930,000 Cfgpd & Stab/NT, R
Tor	4368 -1797	590' SW, ISIP 1499#/30", IFP 152#,
Lans	4496 -1925	FFP 391#, FSIP 1468#/30"
KC	4889 -2318	<u>DST #2 (KC) 4890-4905, Op 2 hrs, GTS/4"</u>
Marm	5070 -2499	Stab @2,830,000 Cfgpd/NT, R 20' SW,
er	5165 -2594	ISIP 1675#/30", IFP 428#, FFP 461#,

(Cont Below)

St G	5360 -2789	FSIP 1670#/30"
Sperg	5620 -3049	<u>DST #3 (St Gen) 5490-5566, Op 1 hr, WB,</u>
LTD	5750 -3179	R 30' M, ISIP 1722#/30", IFP 37#, FFP
		74#, FSIP 1175#/30", RTD 5750, Ran SJ

Log, 5 1/2" @5041 w/150 sx., Perf 12/4892-96 (KC), 500A, OF Ga 2,400,000 Cfgpd/NT, SIP 1409#, Perf 9/4532 (Lans), 2 1/16" tbg to 4880, Pkr @4875, 2nd string 2 1/16" tbg hung @4518, Treat 4532-36 w/1250A, Rec 1d, Ga 1,600,000 Cfgpd, SIP 1240#, Ga 1,400,000 Cfgpd (Lans 4532-36), OF Ga 2,000,000 Cfgpd (KC 4892-96), Cal OF 2,950,000 Cfgpd, SIP 1300#, BTU 952, Lans 4532-36 and Cal OF 2,100,000 Cfgpd, SIP 1400#, BTU 1053, KC 4892-96, Dual Completion - COMPLETED (10-21-64)