

A-9-168

2998 DF

MAP NO. _____ ELEV. 2991 GL
 STATE Kansas COUNTY Stevens SEC. 27 Twp 31 S Rge 35 W
 OPERATOR Mobil Oil Company LOC. C SW NE
 WELL NO. 1 FARM NAME Anderson Trust FT. FROM _____ LINE _____
 POOL Wildcat (PD 6300) FT. FROM _____ LINE _____
 FR. 7-26-61 SPUD 7-26-61 COMP. 9-6-61

CONT./GEOL. Gabbert-Jones Rig # 2 John Benten/Geologist

NAME PRODUCING INTERVAL		COMPLETION RECORD		PERF. W/HOLES	TREATMENT RECORD
FROM	TO				
<u>Mississippian</u>	<u>6003-34</u>		<u>66</u>	<u>500 Ac-F/21.16x7.8</u>	
b					
c					
d					

d I. P. OIL/DIST. F/244 BQ WTR. _____ GAS _____ M.C.F.P.D. _____ CHK. 14/64" HRS. 24
 b " " " " " "
 c " " " " " "
 d

D & A ()

SIP# _____ FI TP # 420 FI CP# 1150 SIBHP _____
 GOR. 332 GR. 41.5° PBD TD 6290
 CEMENT RECORD

SIZE	DEPTH	CASING W/SAX.	SIZE	DEPTH	W/SAX.
<u>8-5/8"</u>	<u>1757</u>	<u>750</u>			
<u>5 1/2"</u>	<u>6267</u>	<u>1200</u>			

OPERATOR Mobil Oil WELL NO. 1 Anderson Trust ELEV. 2998 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Stone Corral	1708	1779	Base Stone Corral	1775	
Wellington	2208		Wellington	2218	
Council Grove	2876		Chase	2598	
Wabaunsee	3255		Winfield	2671	
Heebner	4070		Council Grove	2903	
Lansing	4124		Admire	3162	
Kansas City	4438		Wabaunsee	3301	
Marmaton	4855		Shawnee	3684	
Cherokee	5100		Heebner	4109	
Morrow	5504		Lansing	4171	
Chester	5780		Kansas City	4373	
Ste Genevieve	6047		Marmaton	4918	
St Louis	6097		Cherokee	5123	
			Morrow	5510	
			Chester	5789	
			Ste Genevieve	6054	
			St Louis	6093	

Spud 7-26-61. 8-5/8" @ 1757 w/750 sx.

DST # 1 (KC) 4567-86, op 90 mins, rec 260' GIP + 10' oil + 30'

O&GCWM + 330' SW, ISIP 1356/30 mins, FP 40-158, FSIP 1247/30 mins.

A-9-168

SHEET NO. 2

MAP NO. 307

STATE Kansas COUNTY Stevens SEC. 27 Twp 31 S Rge 35 W

OPERATOR Mobil Oil Company LOC. C SW NE

WELL NO. 1 FARM NAME Anderson Trust

DST # 2 (KC) 4723-45, op 1 hr, rec 1840' GIP + 90' MSGCO + 90' MCSW + 180' SW, ISIP 1385/30 mins, FP 60-110, FSIP 1330/30".

DST # 3 (Chero) 5398-5450, op 1 hr, wk blo died 7 mins, rec 10' M, ISIP 139/30mins, FP 40-40, FSIP 59/30 mins.

DST # 4 (Chest) 5964-93, op 90 mins, GTS 40 mins, ISTM, rec 88' SGCM, ISIP 1461/30 mins, FP 42-42, FSIP 1696/45 mins.

DST # 5 (Chest) 5978-6010, op 190 mins, GTS 1 min, ga 100 MCF, OTS 55 mins, flod 4.6 BO/1 hr, 60/64" ck, gty 39°, rev out, rec 5900' G&O + 90' OCM, ISIP 1770/32 mins, FP 305-1190, FSIP 1795/67 mins.

CORE # 1 (Miss) 6010-69, rec 59' = 3' shly & slty 1m; 15' sd gry & fn to v fn gr, calc, fri, fair poro, gd oil stn & odor & fluor; 41' lm, sdy, gry, very fine xln, dense, no poro, scd oil stn, bldg oil & scd oil odor & fluor.

DST # 6 (Miss) 6015-69, op 1 hr, rec 30' M, ISIP 1542/30 mins, FP 37 to 50, FSIP 953/45 mins.

TD 6290, logs to 6290.

OPERATOR Mobil

WELL NO. 1 Anderson Trust

WLT # 1 (L Chest sd) @ 6031, rec 5800 cc FtW w/scum oil, ISIP 1800/30 mins, FSIP 1800/30 mins.

WLT # 2 (Mann) @ 4958, rec 3500 cc FtW, ISIP 1590/30 mins, FSIP 1530/20 mins.

5½" @ 6267 w/1200 sx. MICT. CO to 6170.

P/40/6024-34. Swb 100 BLO + tr wtr/10 hrs. 500-15% MA. Swb 164 BL/12 hrs. Swb 197 BNO/14 hrs, gty 38.7°.

P/26/6003-16. Swb & flod 80 BL/NT. Trt 6003-34 w/Frac 21,160 oil X 7800 sd. KO & flod 237 BLO + 110 BNO/24 hrs, 14/64" ck, CP 1100, TP 400. (Flod 10 BNOPH last hour)

IP F/244 BOPD, 14/64" ck, FTP 420, FCP 1150, gty 41.5°, GOR 332 from Mississippian (6003-34).

COMPLETE 9-6-61

615949

LIBERAL LOG TOPS

3002 KB

Winfield 2670 (+332)
Council Grove 2914 (+88)
Heebner 4112 (-1110)
Toronto 4130 (-1128)
Lansing 4222 (-1220) tst O&GCXW
Marmaton 4916 (-1914) WLT filt wtr
Morrow 5510 (-2508)
Chester (Opr) 5789 (-2787)
Sand 6000 (-2998) 22/33; flo 244 BO/24 hrs
Ste. Gen 6050 (-3048)
St. Louis 6216 (-3214)
TD 6285