

KANSAS
State Geological Survey
WICHITA BRANCH

WELL COMPLETION REPORT AND
DRILLER'S LOG

S. 36 T. 31 R. 28 ^K W

API No. 15 — 119 — 20389
County Number

Loc. C SW/4 NW/4

County Meade

Operator
Energy Resources Oil & Gas Corporation

Address
2735 Villa Creek Drive, Suite 165, Dallas, TX 75234


Well No. 1 Lease Name Edwards

Footage Location
1980 feet from (N) (X) line 660 feet from (E) (W) line

Principal Contractor Unit Drilling Co. Geologist Warner Sorensen

Spud Date 3-7-80 Date Completed 4-28-80 Total Depth 5660' P.B.T.D. 5483'

Directional Deviation Oil and/or Gas Purchaser Internorth



Locate well correctly
2435'

Elev.: Gr. 2446'
STATE CORPORATION COMMISSION RECEIVED JUL 10 1980 CONSERVATION DIVISION Wichita, Kansas

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4	8-5/8	28	1414'	Lite H	535 150	6% Bentonite 2% Calc. Chl.
Production	7-7/8	4-1/2	10.5	5397'	H	150	2% Gel, 18% Salt .5% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	3-1/8" csg. gun	5302 - 5308

Size	Setting depth	Packer set at
2-3/8"	5280	5283

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 gals 15% acid	5302 - 5308

INITIAL PRODUCTION

Date of first production Waiting on Pipeline	Producing method (flowing, pumping, gas lift, etc.) flowing
RATE OF PRODUCTION PER 24 HOURS	Oil 0 bbls. Gas 530 MCF Water 0 bbls. Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold) Vented	Producing interval (s) 5302 - 5308

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
Energy Resources Oil & Gas Corporation

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.
1

Lease Name
Edwards

Gas

S 36 T 31 R 28 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
	2538		Herrington Ls.	
	2844		Wreford Ls.	
	2944		Council Grove Ls.	
	3080		Cottonwood Ls.	
	3330		Lower Council Grove Ls.	
	3378		Wabaunsee Ls.	
	3505		Tarkio Ls.	
	4212		Heebner Sh.	
	4234		Toronto Ls.	
	4354		Lansing-Kansas City Ls.	
	4924		Marmaton Ls.	
	5075		Cherokee Sh.	
	5256		Morrow Sh.	
	5289		Morrow Sd.	
	5334		Mississippi (Chester) Ls.	
	5470		Ste. Genevieve Ls.	
	5606		St. Louis Ls.	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD

Date Received

Robert B. Baccell
Signature

Operations Manager

Title

July 8, 1980

Date