

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

20-31-29W


Company- NORTHERN NATURAL GAS PRODUCING CO.
Farm- Flagel "A" No. 1

SEC. 20 T. 31 R. 29W
C NW SE

Total Depth. 5755'
Comm. 8-11-57 Comp. 9-9-57
Shot or Treated.
Contractor. Capitt Drlg., Inc.
Issued. 11-15-58

County Meade

KANSAS



Elevation. 2745 RB

Production. 2,033,000 CFC
OPEN FLOW

CASING:

9 5/8" 1657.80' w/800 sx. cem.
5 1/2" 5625.81' w/250 sx. cem.

Figures Indicate Bottom of Formations.

CLAY AND SAND	100
sand gypsum and red bed	595
red bed and shale	833
red bed	960
shale and shells	1017
shell and shale gypsum	1070
sand	1200
shale and shells	1560
shale	1885
shale & lime streaks	2080
shale	2250
shale and lime	2380
lime and shale streaks	2488
lime and shale	2565
lime	2680
lime and shale	2779
lime	2883
lime chert & chalk streaks	2940
lime	3191
lime & chalky lime	3274
lime	3660
chalky lime and lime	3746
lime	3885
lime (chalky)	3975
lime	5283
lime and shale	5346
lime	5438
lime and shale	5450
core #1	5467
Core #2	5511
Core #3	5546
lime	5568
shale and shells	5600
lime and shale	5755 RTD
Total Depth	
TOPS SCOUTS	
Herington	2658
Winfield	2776
Upper Ft. Riley	2833
Pennsylvania	3625
Heebner	4340

Toronto	4365
Lansing	4467
Marmaton	5067
Cherokee	5238
Morrow	5479
Mississippi Chester	5488
Base Uper Chester	5566

