


**

State Ks. Field HOCKETT
 Company NOR. NAT. County MEADE
 Farm FLAGEL "A" No. 1
 Sec. 20 Twp. 31 Range 29

Spot NW SE

Contractor CAPITT

Remarks 6600 MISS.



Comm. 8-11-57 Comp. 11-13-57

Elev. DF 2741 GL 2737 KB TD 5755PB 5594

Pay MISS - 5545 - 46

^{4PTBPT}
 I.P. COF.g. 2, 233 MSF. Press. S.I.P. 1113

Casing Record: 13 3/8 7"

20" 10 3/4 5 1/2" 5626 / 258

16" 9 5/8 1658 / 845

	Sample	Log
\$1590		HER 2658
AUG 21 \$3274 98		WIN 2774
AUG 28 TTD 4718		FTR. 2833
fishing		PENN 3625
SEP 4 rec. \$05467		Heep 4340
SEP 11 \$5450-67 rec.		TOR 4365
17' ; 1'sh, 16'ls		LANs 4467
\$ 5467-5511 rec 43';	$\begin{array}{r} 10 \\ 13 \\ \hline 23 \\ 1 \\ \hline 3 \end{array}$	MARM 5067
6'ls, 1'sh, 13'ls,		Cher 5238
4'sd, 2'ls, 1'sh, 1'ls,		MOR 5479
1'ls trace oil, 1'ls,		CHES. 5488
7'ls oil stain, 1'ls		ST. GEN 5748
oil sat., 1'sh, 1'ls		
1'sh, 2'sh		
DST 5492-5511 op 175"		
GTS 50" TSTM rec 420' SG&MCOil		
FP 50-150 BHP 1200/30		
\$ 5511-46 rec 35' ; 5'sh, 23'ls,		
7'ls sli bleeding gas DST 5522-5600		
op 1 1/2 hrs rec 38' M FP 100-120		
BHP 200/30 RTD 5755 ran log		
WOST		
SEP 18 MICT CO 5594 G/R pf 6/5545		
ran T&PK MA/500 FR/15000 sh/15000		

615632

SEP 25 swab flo 5 BOPH for 36 hr.
GRAV. 29° 1 g 1,630 MCF ~~S.I.P. 1281~~

OCT 2 ✓

OCT 9 ✓


OCT 16 ✓

OCT 23 ✓ OCT 30 ✓ NOV 6 flo 6 BOPH + 450 MCF

~~12/6~~ FCP 950 FIP 658 5 day SICP 1281

SITP 1113 4 TBT COF 2,033 MCF ~~S.I.P. 1281~~

NOV 13 SIP 1113 GOR 20,500 66° gra



AMARILLO TOPS

2745 KB

Heebner 4345 (-1600)

Lansing 4507 (-1762)

Morrow 5480 (-2735)

"S-2" Sd 5490 (-2745) T 10', por 6', tst'd SO&G

Chester 5514 (-2769) tst'd 2,033 MCF

TD 5754 (-3009)