


State KANSAS Field HOCKET
Company W^M GRUENERTWALD County MEADE
Farm GANO No. 1
Sec. 17 Twp. 31 Range 29

Spot SE SW

Contractor GRAHAM - MICHAELIS

Remarks MISS PAN. AM. - DMM



Comm. 8-23-57 Comp. 12-11-57

Elev. DF 2729 GL 2723 KB TD 5550 PB

Pay MISS - 5458-66

^{4PT SPT}
I.P. COF 2,275 MCF Press. RP 1632

Casing Record: 13 3/8 7"

20" 10 3/4 5 1/2" 5549/175

16" 8 5/8 1714/700

	Sample	Log
~~2166~~	MOR 5406	HEEB 4290
SEP 4 ~~3278~~	CH 5452	TOR 4319
SEP 11 ~~4772~~		LANS 4415
SEP 18 ~~5412-51 rec.~~		MARM 5009
31'; 1/2' sh, 1 1/2' sh, 1 1/2' sd,		CHER 5279
4 1/2' ls, 2' sh, 3' sh, 1' ls,		MOR 5404
3' sh, 2' ls, 6 1/2' sh, 1 1/2' ls		CHESTER 5450
2' sh		
~~5453-98 rec. 37' ls,~~		
~~DST 5457-98 (prep)~~		
SEP 25 DST 5457-98		
ap 1 1/2 hr. GTS 1'20"		
TSTM rec 20' M		
FP 10 BHP 1560/psi		
RTD 5550 ran log		
~~5 1/2~~ MICT CO		

pt 64/5458-66 MA/500 swab g 631 MC
FR/7000 SD/3500 2hr BD g 4,500 MC
dry prep to acidize

OCT 2 A/2000 (7 1/2%) swab g 1,500 MCF
Mout CT TST


OCT 9 ✓ OCT 10 ✓ OCT 23 ✓ OCT 30 ✓
NOV 6 ✓ NOV 13 ✓ NOV 20 ✓ NOV 27 ✓

015644

DEC 4 ✓ DEC 11 4 PT BPT 71 DAY SICP 1622

#PT 9 1,232 MCF FCP 734

COF 2,275 MCF RP 1622



AMARILLO TOPS

2732 KB

Heebner 4296 (-1564)

Lansing 4456 (-1724)

Morrow 5404 (-2672) T 11', 7' Tss

"S-2" Sd 5405 (-2673) T 7', por 6', NT

Chester 5415 (-2683) Ø 4,500 MCF

TD 5550 (-2818)