

34 - 31 - 3W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- TENNESSEE GAS TRANSMISSION
Farm- H.C. Altman No. 1

SEC. 34 T. 31 R. 3W
NW NW NW

Total Depth. 4526'
Comm. 10-24-56 Comp. 11-15-56
Shot or Treated.
Contractor. Capitt Drlg., Inc.
Issued. 12-15-56

County Sumner
KANSAS



CASING:
8 5/8" 272.30' w/200 sx cem.

Elevation. 1312' RB

Production. Dry

Figures Indicate Bottom of Formations.

sdv clay	20
shale-red rock	272
shale-shells	870
lime-shale	900
shale-shells	965
lime w/shale brks	1130
lime-shale brks	1275
lime-shale	1395
lime-shale brks	1645
lime-shale	1750
shale	1820
shale-shells	1990
shale-lime	2060
Core #1	2092
shale	2100
shale-lime	2280
lime	2320
lime-shale	2710
shale-shells	2979
lime	3195
shale-lime	3299
lime	3541
shale-lime	3972
lime	4338
shale-lime	4387
lime	4432
shale-lime	4444
shale	4480
shale-lime	4501
lime	4526
Total Depth	

Kinderhook	4328
Simpson sand	4387
Arbuckle	4494

TOPS:

Tarkio	1940
Happy Hollow	2080
Howard (scout)	2129
Topeka	2264
Heebner (scout)	2665
Iatan	2978
Lansing	2987
Kansas City	3290
B/Kansas City	3551
Cherokee	3768
Mississippi	3972

Core - 2061-93 - rec. 20' sh
/ 12' foss lime. Scattered por/
poss. staining.

DST #1 - 2081-92 - open 1 hr.
rec. 68' wtry mud. 15" BHP 730#.

DST #2 - 4388-93 - open 30". Rec.
45' VSO & GCM # 1530' salt wtr.
15" BHP - 1680#.