

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


6-31-3W

Company- AYIWARD ET AL
Farm- Glass No. 1

SEC. 6 T. 31 R. 3W
NE NE SW

Total Depth. 4552
Comm. 2-12-55 Comp. 3-3-55
Shot or Treated.
Contractor. Aylward Drlg. Co.
Issued. 4-2-55

County Sumner
KANSAS



CASING:

8 5/8" 118' cem. w/110 sx

Elevation. 1439 KB

Production. dry

Figures indicate Bottom of Formations.

surface clay	12
sand gravel	75
gravel & redrock	118
redrock	129
redbed	280
shale	820
Anhydrite	870
lime & shale	1030
shale	1070
shale w/lime	1135
shale	1218
lime & shale	1580
shale	1700
lime & shale	1765
sand	1862
sand & shale	1920
sdv shale & lime	2040
lime & shale	2455
lime	2480
lime & shale	3045
lime, shale & sand	3195
sand & shale	3216
lime & shale	3385
lime	3435
lime & shale	3485
lime	3620
lime & shale	4082
lime	4184
lime & shale	4217
lime	4260
lime, sand & shale	4296
lime	4380
shale	4427
sand	4460
shale & sand	4516
sand & Arbuckle lime	4552
Total depth	

Scout Tops:	
Stalnaker	3111
Kansas City	3383
Base Kansas City	3628
Marmaton	3685
Cherokee	3856
Mississippi	4004
Chat	4411
Simpson	4427
Arbuckle	4533

DST 3510-36, open 2 hrs. weak blow rec. 30'
Oil & gas cut mud. BHP Off
4429-35, open 1 hour, rec. 30' muddy wtr
and 40' SW BHP 1650#.