

K. G. S. LIBRARY

KANSAS DRILLERS LOG

Geological Survey
WICHITA BRANCH

JUL 8 0 REG'D

API No. 15 — County — Number

Operator

Texas Oil & Gas Corp.

Address

200 West Douglas, Suite 300, Wichita, KS 67202

Well No.

1

Lease Name

Konecny

Footage Location

660 feet from (N) (S) line 1980 feet from (E) (W) line

Principal Contractor

Slawson Drilling Co.

Geologist

Robert L. Laymon

Spud Date

5-6-79

Total Depth

2360'

P.B.T.D.

2171'

Date Completed

6-5-79

Oil Purchaser


N/A

S. 22 T. 31S R. 3 E W

Loc. 660' FSL & 1980' FWL

County Sumner

640 Acres
N



Locate well correctly

Elev.: Gr. 1319'

DF KB 1325'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8-5/8"		315'		300	
Production		4-1/2"		2202'		150	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A	2 JSPF	N/A	2100-04
TUBING RECORD			2 JSPF	N/A	2106-08'
Size 2-3/8"	Setting depth N/A	Packer set at 2047'			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized with 1000 gallons 15% HCl	At the above
250 gallons acetic acid	intervals listed.

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
P & A	N/A				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	N/A bbls.	N/A	N/A	N/A	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		
N/A			N/A		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Texas Oil & Gas Corp.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.

1

Lease Name

Konecny

Dry Hole

S 22 T 31 R 3 E
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Herington	786	+539		
Winfield	888	+437		
Towanda	963	+362		
Florence	1056	+269		
Wreford	1176	+149		
Cottonwood	1372	-47		
Foraker	1499	-174		
Onaga	1598	-273		
Wabaunsee	1693	-368		
White Cloud	2085	-760		
Howard	2129	-804		
Topeka	2259	-934		
TD	2360			
PBTD	2171			
DST #1, 2048-96', (White Cloud), w/results as follows:				
IFP/30": 42-62#, str blow GTS				
ISIP/60": 753#				
FFP/45": 62-83#, gauge 4 MCF/D				
FSIP/90": 753#				
Rec 215' DM				
DST #2, 2260-85', (Topeka), w/results as follows:				
IFP/30": 10-30#, wk blow incr slightly				
ISIP/60": 957#				
FFP/45": 30-60#, wk blow				
FSIP/90": 957#				
Rec 90' muddy salt water				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received



HAROLD A. BROWN

Signature

District Geologist

Title

June 6, 1979

Date

22-31-3W

DRILLERS LOG

State Geological Survey
WICHITA, BRANCH

OPERATOR: Texas Oil & Gas Corp.
200 W. Douglas, O. W. Garvey Building
Wichita, Kansas 67202

LEASE: Konecny No. 1
C SE SW Sec. 22-31S-3W
Summer County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
200 Douglas Building
Wichita, Kansas 67202

COMMENCED: 5/6/79

COMPLETED: 5/12/70

RTD: 2360'

SURFACE CASING: 8-5/8" set at 320' with 300 sx cement

CONDUCTOR PIPE: 13-3/8" set at 60'


PRODUCTION CSG: 4-1/2" set at 2203' with 150 sx cement

0' to 60' Conductor Pipe
0' to 320' 12 1/4" Surface Hole
139' to 320' Shale
320' to 1920' Shale
1920' to 2285' Shale & Lime
2285' to 2360' Lime
2360' RTD


STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc.
hereby state the above is an accurate copy of the Konecny No. 1 log
for Texas Oil & Gas Corp.


James C. Remsberg

Subscribed and sworn to me this
19th day of May, 1979


Mary Lou Taylor