

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

Photo
22-31-3W

CENTRAL PETRO.CO.,INC.
Stewart No. 1.

SEC.22 T.31 R. 3 W
CS $\frac{1}{2}$ SE NW

Total Depth. 4536'
Comm. 9-25-41 Comp. 11-26-41
Shot or Treated.
Contractor.
Issued. 12-27-41

County. Sumner



CASING:
10 $\frac{5}{4}$ " 595' Cem.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

red rock hrd	80	chert & lime	4230
red bed, shale, shells	155	lime sdy	4250
shale & shells	405	lime & chert	4268
salt & shale	585	lime brkn	4275
shale & shells	616	chert & lime	4278
anhydrite & sand	627	chert	4281
anhydrite & pyrite	665	lime & chert	4284
anhydrite & sdy lime	783	chert	4290
sdv lime & lime	973	lime & chert	4301
sdv lime & pyrite	1010	lime & shale	4372
sdv lime	1195	lime sdy & shale	4400
sdv lime & shale	1253	sand sharp & shale	4425
lime & shale	1678	lime & shale	4433
lime & red rock	1810	sand & shale	4459
lime & shale	2135	sand hd & shale,	
lime brkn	2210	pyrite in shale	4490
shale & red rock	2268	pyrite & sand hd	4501
lime	2350	sand & pyrite	4506
lime & shale	2447	Arbuckle dolomite &	
lime	2505	chert	4514
shale & red rock	2641	Arbuckle lime & chert	4536
shale & lime	2742	Total Depth.	
lime	2770		
shale, red rock, lime	2838	shale sticky, lime hd	3678
shale & lime	2895	shale & lime hd	3708
shale sticky	2996	shale sticky, lime hd	3802
sdv shale, red rock	3048	shale sticky, lime	3835
shale & lime	3097	lime cherty, shale	3938
lime	3110	shale & lime	3967
lime sdy	3125	chert	3969
shale & lime	3136	lime	3976
shale, little lime	3220	chert, chat, dolomite &	
shale & lime	3295	lime hd	4011
lime K.C.	3340	chert & lime hd	4027
lime sft	3352	lime cherty & shale	4047
lime K.C. hrd	3372	lime cherty, sharp	4078
chert & lime	3413	lime sdy	4154
lime	3436	chert & lime sdy	4195
lime brkn	3492	chert & lime sdy hd	4209
lime	3539		
lime brkn	3561		
shale sticky	3589		