

State Geological Survey
WICHITA, BRANCH

KANSAS DRILLERS LOG

API No. 15 — ¹⁷⁵ Seward — 20285
County Number

S. 7 T. 31S R. 31W E
Loc. SE SE SE Sec. 7-31S-31W
County Seward

Operator
Woods Petroleum Corporation

Address
3555 N.W. 58th Street, Oklahoma City, Oklahoma 73112


Well No. 1 Lease Name Schmidt

Footage Location
feet from (N) (S) line feet from (E) (W) line

Principal Contractor Triad Drilling Geologist Don Huber

Spud Date 5-9-76 Total Depth 5620' P.B.T.D.

Date Completed 7-21-76 Oil Purchaser



Locate well correctly
Elev.: Gr. 2830
DF KB 2840

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
	12 1/4"	8 5/8"	24#	1400'	Litewate Class "H"	550 sx 200 sx	2% cc 2% cc
		4 1/2"	11.60#	5590'	Pozmix	300 sx	18% salt, 12 1/2% Gtl/sx. 3/4 1%

RECEIVED
STATE CORPORATION COMMISSION

OCT 05 1976
LINER RECORD

PERFORATION RECORD

Top, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
		2 spf		4958-62'

CONSERVATION DIVISION
Wichita, Kansas

TUBING RECORD

Size	Setting depth	Packer set at
2 3/8"		5430'

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 gal. 7 1/2% MCA	5468-72
12,000 gal 3% A/Wtr. 10,000# 20/40 sand	5468-72

INITIAL PRODUCTION

Date of first production 7/21/76 Producing method (flowing, pumping, gas lift, etc.) Flowing

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	<u>trace</u> bbls.	<u>620</u> MCF	<u>nil</u> bbls.	CFPB

Disposition of gas (vented, used on lease or sold) No market yet Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Woods Petroleum Corporation		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name Schmidt	Gas
S _____ T _____ R _____ E _____ W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	_____
	Signature

	Title

	Date
