

17-31-31W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MAGNOLIA PETROLEUM COMPANY
Farm-O.L. GARTEN Unit No. 1

SEC. 17 T. 31 R. 31W
NE NE SW

Total Depth. 5702
Comm. 6-27-57 Comp. 8-12-57
Shot or Treated.
Contractor. Gabbert-Jones Drlg.
Issued. 11-30-57

County Seward
KANSAS



Elevation. 2837

Production. Dry

CASING:
9 5/8" @ 756' & cem. w/450 sx.
5 1/2" @ 2826' & cem. w/750 sx.

Figures indicate Bottom of Formations

surface clay	120
sand	300
shale & shells	545
red bed	1100
red shale & sand	1675
shale & lime	2087
shale & shells	2300
shale & lime	2525
shale	2613
lime & shale	2730
lime	2850
lime & shale	2955
lime	3003
shale & lime	4085
lime	4260
lime & shale	4355
lime	4535
lime & shale	4605
lime	4881
lime & shale	4930
lime	4980
lime & shale	5080
lime	5145
lime & shale	5220
lime	5300
lime & shale	5385
lime	5515
shale & lime	5625
lime	5702
Total Depth	

TOPS: SCOUT	
Herington	2655
Heebner	4212
Lansing Kansas City	4335
Base Kansas City	4981
Marmaton	4959
Cherokee	5126
Morrow	5442
Morrow sand	5474
Chester	5527
Sant Genive	5667

DST #1, 2620-2763 open 1 hr., 1t blow, rec, 60' DM NS, FF 50#, BHP 230#, SI 20 min.

DST #2, 5432-5515, open 1 hr. poor blow throughout test, rec, 25' DM NS IF 25#, FF 35#, IBHP 75#, SI 20 min. FBHP 160# SI 20 min.

DST #3 straddle packed interval 5409-5444, open 1 hr. 1t blow 20 min. pulled packers loose and stuck bottom packer @ 1210' FFP 25# BHP 35#

R F D