

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


10-31-32W

Company- SKELLY OIL CO.
Farm- L. L. Burr No. 1

SEC. 10 T. 31 R. 32W
SW SW NE
330' f SL & 330' f WL NE/4

Total Depth. 2712
Comm. 9-19-51 Comp. 9-26-51
Shot or Treated.
Contractor. Flournoy Drlg.
Issued. 2-23-52

County Seward
KANSAS



CASING:

10 3/4" 687' cem. w/500 sx.
7" 2700 cem. w/350 sx.

Elevation. 2858 D.F.

Production. 4,800,000 gas

Figures Indicate Bottom of Formations.

surface soil & clay 105
sand 360
sand, shale & shells 510
clay gry, red bed &
sand 560
shale red & lime 690
red bed & gyp 790
red bed & sand 1035
anhyd. 1150
red bed & sand 1680
red bed 1880
red bed & shale grn 2125
shale & shells 2340
shale & lime 2475
shale & anhyd. 2594
cream, lgt gry, fine,
granular chy dolo. 2604
lime & shale 2623
dolo. gry, fine & gran-
ular 2630
lime & shale 2656
gry, fine xyn, pinhole
por., slightly chy.
dolo. 2671
lime 2694
dolo. gry, fine xyn,
slightly porous 2700
dolo. 2712
Total Depth

Tops:

Herrington 2594
Upper Arider 2622
Lower Arider 2644
Winfield 2694

Producing formations:

Herrington 2594-2604
Arider lime 2622-2676
Winfield lime 2700-2712

Acid:

10-7-51 1000 gals. 2700-2712
10-8-51 4000 " 2700-2712
10-10-51 1000 " 2644-2676
10-11-51 1000 " 2622-2640
10-12-51 1000 " 2594-2604
10-13-51 10,000 gals. 2644-76
10-15-51 9,000 " 2644-76 2622-40,
2594-2604