

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOGA No. 15 — 175 — 20 481
County Number

Operator

Rincon Operating Company

Address

1580 Lincoln St. #700, Denver, CO 80203

Well No.

1

Lease Name

Whitney #1

Footage Location

660

feet from (N) (S) line

660

feet from (E) (W) line

Principal Contractor

DeMac

Geologist

Spud Date

9/ /80

Date Completed

11/7/80

Total Depth

5560'

P.B.T.D.

5508'

Directional Deviation

None Taken


Oil and/or Gas Purchaser

CIG

State Geological Survey
S. 12 T. 31S R. 32 E W

Loc. SE SE

County Seward

640 Acres
N

Locate well correctly

Elev.: Gr.

2829

DF KB 2838

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface csg	12 1/4'	8 5/8"	24	1521'	Lite & Regular	450&200sxs	2% CaCl2
Production csg	7 7/8"	4 1/2"	10.5	5550'	50/50 Poz	250 sxs	

LINER RECORD

PERFORATION RECORD

Tr.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4 JSPF	3 1/8" JS	5341' to 5345'
TUBING RECORD					
Size	Setting depth	Packer set at			
2 3/8"	5364'	---			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1000 gals. 7 1/2% HCl	5341' to 5345'

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
11/7/80	Flowing				
RATE OF PRODUCTION FOR 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	---	2,000 MCF	---	---	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
to be sold			5341' to 5345'		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.

1

Lease Name

Whitney

Gas

S 12 T 31S R 32 E

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

Red Bed Sand

0

730

Red Bed

730

1320

Red Bed- Anhydrite

1320

1531

Shale - Anhydrite

1531

2260

Shale

2260

2338

Lime - Shale

2338

5552

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature

Agent

Title

11/19/80

Date

WELL LOG

COMPANY Rincon Operating Comany

SEC. 12 T. 31S R. 32W

FARM Whitney

NO. 1

LOC. SE SE

TOTAL DEPTH 5552 RTD


COUNTY Seward, Kansas

COMM. 7-28-80

COMP. 10-12-80

CONTRACTOR DaMac Drilling Inc.

CASING 8 5/8 set @ 1521



ELEVATION

PRODUCTION 4½ set @ 5550

FIGURES INDICATE BOTTOM OF FORMATIONS

RedBed, Shand	0	730
RedBed	730	1320
RedBed, Anhydrite	1320	1531
Shale, Anhydrite	1531	2260
Shale	2260	2338
Lime, Shale	2338	5552 RTD