


Company- STANOLIND OIL & GAS CO.
 Farm-Lower Gas Unit No. 1

SEC. 18 T. 31 R. 32W
 C W/2 W/2 NE
 1320' S of NL, 2590' W of EL

Total Depth. 2706
 Comm. 11-12-54 Comp. 12-6-54
 Shot or Treated.
 Contractor.
 Issued. 1-8-55

County Seward
 KANSAS



Elevation. 2868 DF

Production. 4,170,000 Gas

CASING:

8 5/8 @ 578' w/ 400 sx cmt.
 5 1/2 @ 2681' w/ 1000 sx cmt.

Figures Indicate Bottom of Formations.

surface sand & clay	423
sand & clay	523
clay & shale	579
red bed	979
shale & anhydrite	2208
anhydrite & lime	2562
lime	2706
Total Depth	

TOPS:

Herrington	2603
Krider	2644
Winfield	2685

Schlumberger ran Gamma Ray & Micro-Log.

Acidized:

Winfield 250 gal J-type acid 15%,
 3500 gal B-type acid 12%, 1750 gal.
 J-type acid 7½%, flushed 2750 gal.
 water
 Krider 250 gal J-type acid 15%, 3000
 gal B-type acid 12%, 1500 gal J-type
 acid 7½%, flushed 2730 gal water
 All zones 8000 gal. 7½% J-type acid
 flushed 2750 gal water
 Herrington 250 gal J-type acid 15%,
 2000 gal B-type acid 12%, 1000 gal
 J-type acid 7½%, flushed 2689 gal.
 water
 All zones, 4000 gal 7½% J-type acid,
 flushed 2750 gal water.

Perf. 6 SPF:

Krider 2644-62
 Herrington 2606-14, 2620-24