

23-31-32W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SKELLY OIL COMPANY
Farm- Ira Chapple No. 1


SEC. 23 T. 31 R. 32W

SE SE NW NW

1250' fr NL & 1250' fr WL sec.
23

County Seward
KANSAS

Total Depth. 2736
Comm. 11-29-53 Comp. 12-18-53
Shot or Treated.
Contractor. Walter Kuhn Drlg. Co.
Issued. 3-6-54



CASING:

10 3/4" 705' cem. w/400 sx
7 5/8" 2623' cem. w/700 sx
5 1/2" 2726'

Elevation. 2853 DE

Production. 5,200,000 Gas

Figures Indicate Bottom of Formations.

surface soil, sand &	
clay	520
red bed	706
shale & red bed	1520
shale	1630
shale & anhydrite	1720
shale & lime	2210
shale	2335
lime & shale	2537
lime	2625
lime	2633
shale	2643
lime	2706
shale	2725
lime	2736
Total Depth	

Tops:	
Hollenberger Lime	2556
Herington Lime	2623
Paddock Shale	2630
Upper Krider	2647
Krider Shale	2668
Lower Krider	2672
Winfield	2725

Producing Formation:
Hugoton Gas Pay 2623-2736'

12-19-53 shot acid between
2623-2736' w/3000 gals.
12-20-53 shot 6000 gals.
acid between 2623-2736'
12-22-53 shot 4000 gals.
acid between 2623-2736'
12-23-53 shot 10,000 gals.
acid between 2623-2736'