


A-10-136

MAP NO. K-24 ELEV. 2839 DF
 STATE Kansas COUNTY Seward SEC. 12 Twp 31S Rge 32W
 OPERATOR Lario Oil & Gas Company LOC. C SW/4
 WELL NO. 1 FARM NAME Luther-Schmidt GU FT. FROM _____ LINE _____
 COL Hugoton (PD 2700) FT. FROM _____ LINE _____
 FR. 8-23-61 SPUD 8-22-61 COMP. 9-28-61
 CONT./GEOL. K & E Drlg Tools Rig #3



COMPLETION RECORD			
NAME PRODUCING INTERVAL	FROM - TO	PERF. W/HOLES	TREATMENT RECORD
<u>Permian</u>	<u>2618-46</u>	<u>64</u>	<u>1000Ac, F/12x12</u>
b			
c			
d			

a I. P. OIL/DIST. _____ WTR. _____ GAS 3210 MCF/PD _____ CHK. _____ HRS. _____
 b " " " " " " " " " "
 c " " " " " " " " " "
 d _____

D & A ()

SIP# 330 FI TP # _____ FI CP# _____ SIBHP _____
 GOR. _____ GR. _____ PBD 2660 TD 2668

CASING - CEMENT RECORD		
SIZE	DEPTH	W/SAX.
<u>8 5/8"</u>	<u>618</u>	<u>300</u>
<u>5 1/2"</u>	<u>2664</u>	<u>525</u>

OPERATOR Lario Oil & Gas Co. WELL NO. #1 Luther-Schmidt GU ELEV. 2839 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
<u>Herrington</u>	<u>2604</u>		<u>Herrington</u>	<u>2605</u>	
<u>1st Krider</u>	<u>2628</u>		<u>Upper Krider</u>	<u>2628</u>	
<u>2nd Krider</u>	<u>2668</u>		<u>Lower Krider</u>	<u>2668</u>	

Spud 8-22-61. 8 5/8" @ 618 w/300 sx.
 TD 2668. Logs to 2667. 5 1/2" @ 2664 w/525 sx. GR-N logs. DD to 2676.
 (OH fr 2664-76) Ga 30 MCF, 500 MA, Ga 1390 MCF/10 hrs. Flowed 1d., Frac 12,000 Ac X 12,000 sd. Ga 4402 MCF + 9 BLPD. PB to 2654.
 P/16/2618-22, 48/2634-46, Ga 295 MCF, 750 MA, Flod 3 BWPH w/3038 MCF. CO to 2676, 250 MA, Frac 12,000 Ac X 12,000 sd. Ga 740 MCF w/1d. PB to 2660. 14 1/2 hr SICP 330. 72/20 Ga 5690 MCF.
 IP (Company Test) 3210 MCF, SIP 330, from Permian (2618-46).
 COMPLETE 9-28-61.

LIBERAL LOG TOPS

2839 DF

Krider 2628 (+211) ϕ 3,210 MCF
TD 2670