


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E. Mardock, Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Conover "B" No. 1

6
SEC. 7 T. 31 R. 33W
SE 31 NW
100' N & 100' W of CEN

County. Seward

KANSAS



Total Depth. 2760
Comm. 6-14-49 Comp. 6-21-49
Shot or Treated. Acid 28,500 gals.
Contractor. Lohmann-Johnson Drilg.
Issued. 2-18-50

CASING:

8 5/8" 640' cem. w/300 sx.
5 1/2" 2759' cem. w/875 sx.

Elevation. 2941.2nd.

Production. 30,400,000 gas

Figures Indicate Bottom of Formations.

surface soil & sand	65
sand & shale	125
sand	400
sand & shale	505
shale	620
red bed	800
shale & shells	1025
shale	1155
anhyd.	1200
shale & shells	1865
lime & shale	1955
shale & shells	2035
shale, shells, & red bed	2135
shale & shells	2302
lime	2560
lime & shale	2625
lime	2760
Total Depth	

Perf.	110 shots	2662-2684
	140 "	2618-46
	40 "	2600-2608
	20 "	2590-94
	30 "	2567-73

7-6-49	1250 gals.	15% acid	2567-2608
"	1750 "	" "	2618-46
"	1500 "	" "	2662-84
7-7-49	9000 "	" "	2567-2646
"	4500 "	" "	2662-84
"	5500 "	" "	2712-40
7-9-49	9000 "	5% "	to all zones.

Tops:
Herrington 2566
Upper Krider 2592
Lower " 2612
Winfield 2662
Upper Fort Riley 2709

Ran Halliburton electric log.

Found hole in casing at 600'. Drilled
cem. out of 5 1/2" casing from 602' to 2755'.

Perf. 140 shots 2712-40; 3,550,000 gas
7-3-49 2000 gals. 15% acid 2712-40; 17000
MCF gas.