


WELL LOG BUREAU-KANSAS GEOLOGICAL SOCIETY 14-31-33W
 508 East Murdock, Wichita, Kansas

Company- STANOLIND OIL & GAS CO.
 FarmAngell Gas Unit No. 1

SEC. 14 T. 31 R. 33W
 SW SW NE
 150' N of SL 150' E of WL

Total Depth. 2722 PBD 2690
 Comm. 9-3-52 Comp. 10-10-52
 Shot or Treated.
 Contractor.
 Issued. 1-10-53

County Seward
 KANSAS



CASING:
 10 3/4 592w/ 400 sx cement
 7" 2698w/ 300 sx cement

Elevation. 2879

Production 3,407,000 Gas

Figures Indicate Bottom of Formations.

clay & sand	90		
sand	180		
clay & gyp	310		TOPS
sand	345	Herington	2616
clay & sandrock	520	Krider	2655
red bed	630	Winfield	2698
sand	660		
red bed	800		
red rock	1160		
red rock & sand	1440		
red rock & salt	1680		
anhydrite	1765		
red rock	1860		
red rock & gyp	1935		
red rock	2130		
anhydrite	2270		
red rock	2335		
anhydrite	2355		
shale & anhydrite	2455		
anhydrite	2560		
anhydrite & lime	2610		
lime	2722	T. D.	

Perofrated w/ 6 shots per ft. as follows

Herington 2616-22, 2627-31, 2633-37, 2639-45, 2648-50.
 Krider 2658-69, 2673-78.

Acidized as follows

Winfield	2500 gal 15%
Herington	2000 gal 15%
Krider	1500 gal 15%