

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock,
Wichita, Kansas


14 - 31 - 33W

Company- PAN AMERICAN PETROLEUM CORP.
Farm- Angell Gas Unit "A" No. 2

SEC. 14 T. 31 R. 33W
C SW/4
1320 N of SL, 1320 E of
WL of SW/4

County Seward
KANSAS

Total Depth. 2707' PB 2690'
Comm. 6-21-57 Comp. 6-27-57
Shot or Treated.
Contractor.
Issued. 9-7-57



Elevation. 2885' DF

Production. 3,840,000 MCFG

CASING:

8 5/8" 614' cem w/400 sx.
5 1/2" 2702' cem w/800 sx.

Figures indicate Bottom of Formations.

sand & shells	547
sand & shale	580
red bed	800
sand & shale	1205
shale	1385
shale & shells	2200
shale	2260
shale & shells	2390
lime	2524
anhydrite & shale	2600
lime	2707

Total Depth

Plug back to 2690'

TOPS:

Herington	2624
Krider	2664
Winfield	2698

Ran Electric log.

Sch. Perf. 2664-66' and 2676'78' with
10 shots per foot. No gas.
Perf. 2632-40' with 6 shots per foot.