

20-31-33W

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CITIES SERVICE OIL CO.

FARM Salley "B" NO. 1


SEC. 20 T. 31 R. 33W

LOC. SE SE NW

100' W. & 300' N
of center

COUNTY Seward

KANSAS



TOTAL DEPTH 2710'

COMM. 9-5-49

COMP. 9-11-49

SHOT OR TREATED

CONTRACTOR Lohmann & Johnson

ISSUED 6-2-51

CASING

8 5/8" 565' cem w/300 sxs.
5 1/2" 2709' cem w/700 sxs.

ELEVATION 2898

PRODUCTION 11,300,000 gas

FIGURES INDICATE BOTTOM OF FORMATIONS

surface soil	105
sand & gravel	275
sand & shale	520
red bed	615
shale & shells	1075
anhydrite	1165
red bed	1200
shale & shells	2112
shale & lime	2545
lime & shale	2710
Total depth	

Tops:

Herington	2566
Upper Krider	2596
Lower Krider	2623
Winfield	2668

Perforated:

40 shots	2592-2600
145 shots	2624-53
115 shots	2670-93

SIP 408.3#

Ran Halliburton electric log.