

21-31-33W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- STANOLIND OIL & GAS CO.
Farm- Becker Gas Unit No. 1
"B"

SEC. 21 T. 31 R. 33W
SW SW SW NE
150' N of SL 150' E of VL
NE $\frac{1}{4}$
County Seward
KANSAS


Total Depth. 2756
Comm. 6-28-51
Shot or Treated.
Contractor.
Issued. 10-27-51

Comp. 7-12-51

CASING:

10 3/4" 583' cem. w/450 sx
6 5/8" 2740' cem. w/300 sx

Elevation. ~~2887~~ (m)
2884
2888' and
Production. 15,265,000 G.



Figures indicate Bottom of Formations.

surface clay	80
sand	310
clay & sand	480
red bed	990
anhy.	1030
anhy. & gyp.	1100
shale	1435
anhy. & lime	1745
lime & shale	2020
anhy. & lime	2045
shale & lime	2237
lime	2605
lime & dolo	2737
lime	2756
Total Depth	

Tops:	
Hollenberg	2579
Herington	2609
Krider	2619
Winfield	2696
Towanda	2738

Schlumberger run to 2756

Lane-Wells Gun Perforated
w/6 SPF as follows:

Winfield	2696-2712
Krider	2649-2656
Herington	2660-2672
Herington	2617-2637

Dowell Inc. Acidized as follows:

Towanda w/1000 gal 15%
flushed w.3900 gal wtr.

Winfield w/1500 gal. 15%
flushed w/650 gal. wtr.

Krider w/2000 gal. 15%
flushed w/650 gal wtr.

Herington w/2000 gal. 15%
flushed w/650 gal. wtr.
w/9000 gal. 7 1/2% flushed
w/3900 gal. wtr.
w/6000 7 1/2% flushed
w/2900 gal. wtr.