

30-31-33W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Beaty "C" No. 1

SEC. 30 T. 31 R. 33W
NW SW SE NE
600' W & 350' N of Cen.

Total Depth. 2732

Comm. 8-26-49

Comp. 9-2-49


Shot or Treated. 16,000 gals. 15%

Contractor. Lohmann-Johnson Drlg.

Issued. 2-18-50

County. Seward

KANSAS



Elevation. 2846 Ind.

Production. 11,300,000 gas
20 min. O.F.

Figures Indicate Bottom of Formations.

surface soil	65
sand & shale	190
sand & gravel	250
sand & shale	480
red bed	565
shale & shells	1045
anhyd.	1110
redbed	1150
shale & shells	2320
lime & shale	2547
lime	2590
lime & shale	2700
lime	2732
Total Depth	

Tops:

Herrington	2529
Upper Krider	2558
Lower "	2584
Winfield	2629
Upper Fort Riley	2686

Ran Halliburton electric log.

Perforating Record

90 shots 2630-2648

140 shots 2584-2612

40 shots 2530-2538

Acidizing Record

9-13-49 500 gals. 15% acid 2530-38

" 1500 " " " 2584-2612

" 1000 " " " 2630-48

" 7000 " " " 2530-2612

" 3000 " " " 2630-48

9-16-49 9000 " 5% acid to all zones.